# ALDEN

Verification Testing of the Lane Enterprises SK75 Stormkeeper Chamber Sediment Strip and Prinsco Hydrostor HS75 Sediment Row In Accordance with the NJDEP Laboratory Protocol to Assess Total Suspended Solids Removal by a Filtration Manufactured Treatment Device, 2013

> Technical Evaluation Report Alden Report No. : 1162LESSCSVT

> > Submitted to:

Lane Enterprises Camp Hill, PA

Prepared by

James Mailloux Senior Engineer Alden Research Laboratory

October 2016

ALDEN Research Laboratory, Inc. 30 Shrewsbury Street, Holden, Massachusetts 01520-1843 508-829-6000/phone • 508-829-5939/fax info@aldenlab.com • www.aldenlab.com

# TABLE OF CONTENT

1.0	INTRO	DUCTION 1
2.0	TEST	UNIT DESCRIPTION Error! Bookmark not defined.
3.0	MATE	RIALS and METHODS 4
3.1	EXF	PERIMENTAL DESIGN 4
3	.1.1	Hydraulic Testing 5
3	.1.2	Removal Efficiency Testing
3.2	INS	TRUMENTATION AND MEASURING TECHNIQUES7
3	.2.1	Influent Flow
3	.2.2	Drawdown Flow
3	.2.3	Temperature
3	.2.4	Pressure Head
3	.2.5	Sediment Injection
3	.2.6	Sample Collection
3	.2.7	Sample Concentration Analyses11
3.3	DAT	TA MANAGEMENT AND ACQUISITION12
3.4	PRE	EPARATION OF TEST SEDIMENT13
3.5	DAT	ΓΑ ANALYSIS14
3	.5.1	Hydraulics
3	.5.2	Removal Efficiency
3.6	LAE	BORATORY ANALYSIS
3.7	QU	ALITY ASSURANCE AND CONTROL16
3	.7.1	Flow
3	.7.2	Sediment Concentration Analysis17
4.0	RESU	LTS AND DISCUSSION17
4.1	SED	DIMENT REMOVAL PERFORMANCE17
4.2	Hyd	raulic Measurements
5.0	CONC	LUSIONS
Apper	ndix A	ALDEN QUALIFICATIONS24
Apper	ndix B	Instrumentation Calibrations25

# TABLE OF FIGURES

Figure 1: Drawing of the SK75 Treatment Unit	2
Figure 2: Lane SK75 Test Unit Installed in the Test Tank Prior to Backfilling	3
Figure 3: Lane SK75 Test Unit Fully Installed in the Test Tank	3
Figure 4: Photograph of the Test Set Up	4
Figure 5: Plan View of Alden Flow Loop	5
Figure 6: Photograph Showing Laboratory Flow Meters	7
Figure 7: Photograph Showing Laboratory Pumps	8

Figure 8: Drawdown V-notch Weir Flow vs Head Curves	8
Figure 9: Pressure Measurement Instrumentation	9
Figure 10: Photograph Showing Variable-speed Auger Feeder	10
Figure 11: Photograph Showing the Background Isokinetic Sampler	10
Figure 12: Laboratory Sample Filtration Equipment and Scale	12
Figure 13: Sample Analysis Laboratory Equipment	12
Figure 14: PSD Curves of 1-1000 micron Test Sediment and NJDEP Specifications	14
Figure 15: Lane SK75 Removal Efficiency and Influent Concentration Curves	19
Figure 16: Lane SK75 Hydraulic Characteristic Curves	20



# LIST OF TABLES

Table 1: Test Sediment Particle Size Distribution	6
Table 2: PSD Analyses of Alden NJDEP 1-1000 Mix	13
Table 3: Removal Efficiency Summary	18
Table 4: Measured Influent Parameters	18
Table 5: Measured Sample Concentrations	19
Table 6: Measured Hydraulic Data	20

## **1.0 INTRODUCTION**

Under a contract from Lane Enterprises (Lane), verification testing was conducted on the Lane Enterprises SK75 Stormkeeper Chamber Sediment Strip and Prinsco Hydrostor HS75 Sediment Row treatment system, at Alden Research Laboratory, Inc. (Alden), Holden, Massachusetts.

The purpose of the testing was to define the performance characteristics of the sediment strip chamber under controlled laboratory conditions, utilizing established standard testing methodologies. The testing was conducted in accordance with "New Jersey Department of Environmental Protection Laboratory Protocol to Assess Total Suspended Solids Removal by a Filtration Manufactured Treatment Device", 2013, to establish the following parameters:

- a) Hydraulic Characteristic Curves:
- b) Sediment Removal Efficiency at Maximum Treatment Flow Rate (MTFR)
- c) Filter Blinding (Occlusion) or maintenance statement.
- d) At a minimum, the particle size distribution of the influent material for sediment test conditions.

## 2.0 TEST UNIT DESCRIPTION

The tested treatment chamber was an arched stormwater detention/retention sediment collection and filtering device, measuring approximately 51" wide x 30" high x 7 ft long. Both ends of the chamber were sealed with the use of end caps. A water-tight tank was used to house the test chamber system. The chamber was installed on top of a 1-ft base of  $\frac{3}{4}$ "-2" double-washed stone containing a 6" underdrain pipe, which penetrated the downstream tank wall. Two layers of woven Geotextile fabric were placed between the stone base and chamber to collect particulate contaminants, as well as protect the stone base from scouring. The fabric had an open-area of 1% and opening size of 425 microns. The top fabric layer was used to fully wrap the chamber and end caps. The chamber floor filtration area was approximately 30 ft<sup>2</sup>. Water was conveyed into the chamber by means of a 12" inlet pipe, which penetrated the upstream end cap. The junction was wrapped in non-woven fabric. The invert of the pipe was approximately flush with the chamber floor. Additional stone was installed around the outside of the chamber until fully buried. A 4-inch x 2-ft tall PVC standpipe was installed into the crown of the chamber. In a typical installation, water passing through the base fabric seeps into the stone base and is either re-infiltrated into the surrounding soil, enter the underdrain and is conveyed into an outlet control structure, or is distributed into other chambers in the stormwater management system. Although the primary function of the sediment strip chamber is to capture and retain sediment particles, the Geotextile membrane possesses filtering characteristics and therefore, was tested as such. On-line scour testing was not conducted, as the system is designed for an off-line application with the inclusion of an upstream bypass weir. The weir was not included in the laboratory set-up.

11.6"

[295mm]

Drawings of the SK75 test unit are shown on **Figure 1**. A Photograph showing the wrapped unit installed in the test tank is shown on **Figure 2**. The final installation is shown on **Figure 3**. A photograph of the test loop is shown on **Figure 4**.

Chamber Specifications							
Chamber Slze (L x W x H)	87.1" x 51.0" x 29.7" (2,212 x 1295 x 754 mm)						
Installed Length	84.9" (2,156 mm)						
Chamber Storage	46,4 ft <sup>3</sup> (1,31 m <sup>3</sup> )						
Min. Installed Storage*	74.9 ft <sup>3</sup> (2.12m <sup>3</sup> )						
Welght / Chamber	70 lbs (32 kg)						
Chambers / Pallet	33						
Approx, Weight / Pallet	2,500 lbs (1,134 kg)						



**End Cap Specifications** 

End Cap Slze (L x W x H)

Installed Length

End Cap Storage

Min. Installed Storage\*

Weight

11.6" x 48.1" x 29.4" (295 x 1,222 x 747 mm)

> 8.0" (203 mm) 2.75 ft<sup>3</sup> (0.08 m<sup>3</sup>)

12.02 ft3 (0.34 m3)

12 lbs (5.44 kg)



Figure	1.	Drawing	of	tho	SK75	Treatment I	Init
Figure	1.	Diawing	UI.	uie	31/3	rieauneni	Jint

48.1"

[1222mm]



Figure 2: Lane SK75 Test Unit Installed in the Test Tank Prior to Backfilling



Figure 3: Lane SK75 Test Unit Fully Installed in the Test Tank



Figure 4: Photograph of the Test Set Up

# 3.0 MATERIALS AND METHODS

## 3.1 EXPERIMENTAL DESIGN

The SK75 test unit was installed in the Alden test loop, shown on **Figure 5**, which is set up as a recirculation system. The loop is designed to provide metered flow up to approximately 17 cfs. Flow was supplied to the unit with one or two selected laboratory pumps (20HP, 50HP), drawing water from a 50,000-gallon supply sump. The test flow was set and measured using one of five differential-pressure meters and corresponding control valves. A Differential Pressure (DP) cell and computer Data Acquisition (DA) program was used to record the test flow. 25 feet of straight 12-inch PVC influent pipe conveyed the metered flow to the unit. 2 feet of 6-inch PVC pipe free-discharged the effluent flows to a receiving tank, which contained a calibrated V-notch weir at the downstream end for measuring drawdown flow. The influent and effluent pipes were set at 1% slopes. A 12-inch tee was located 4 pipe-diameters (4 ft) upstream of the test unit for injecting sediment into the crown of the influent pipe using a variable-speed auger feeder.

Filtration of the supply sump, to reduce background concentration, was performed with an insitu filter wall containing 1-micron bag filters.



Figure 5: Plan View of Alden Flow Loop

## 3.1.1 Hydraulic Testing

The SK75 unit was tested with clean water to determine its hydraulic characteristic curves, including loss coefficients (Cd's) and/or K factors. Flow and water level measurements were recorded during steady-state flow conditions using a computerized Data-Acquisition (DA) system, which included a data collect program, 0-250" Rosemount Differential Pressure (DP) cell (flow), and Omegadyne PX419 0-2.5 psi Single-ended Pressure (SP) cell (water elevations). Flows were set and measured using the calibrated flow meters and control valves. Each test flow was set and operated at steady state for approximately 10 minutes, after which time a minimum of 30 seconds of flow and pressure data were averaged and recorded for each pressure tap location. Water elevations were measured above and below the fabric layer outside of the chamber. Measurements within the influent and effluent pipes were taken one pipe-diameter upstream and downstream of the unit.

## 3.1.2 Removal Efficiency Testing

Sediment testing was conducted to determine the removal efficiency, as well as sediment mass loading capacity.

The sediment testing was conducted on an initially clean system at the 100% MTFR of 120 gpm (as selected by Lane). A minimum of ten 30-minute test runs were required to be conducted. The captured sediment was not removed from the chamber between tests.

The total mass injected into the system was quantified at the conclusion of the 10 runs. This data was used for determination of the required maintenance frequency.

The test sediment was prepared by Alden to meet the PSD gradation of 1-1000 microns in accordance with the distribution shown in column 2 of **Table 1**. The sediment is silica based, with a specific gravity of 2.65. Three random PSD samples of the test sediment were analyzed by an independent certified analytical laboratory using ASTM D 422-63 (Reapproved 2007) "Standard Test Method for Particle Size Analysis of Soils". The average of the three samples was used for compliance with the protocol. Additional discussion of the sediment is presented in Section 3.4.

Table 1: Test Sediment Particle Size Distribution <sup>1</sup>						
Particle Size (Microns)	Target Minimum % Less Than <sup>2</sup>					
1,000	100					
500	95					
250	90					
150	75					
100	60					
75	50					
50	45					
20	35					
8	20					
5	10					
2	5					
<ol> <li>The material shall be hard, firm, and inorganic with a specific gravity of 2.65. The various particle sizes shall be uniformly distributed throughout the material prior to use.</li> <li>A measured value may be lower than a target minimum % less than value by up to two percentage points, A measured value may be lower than a target minimum % less than value by up to two percentage points (e.g., at least 3% of the particles must be less than 2 microns in size [target is 5%]), provided the measured d50 value does not exceed 75 microns.</li> </ol>						

#### **Table 1: Test Sediment Particle Size Distribution**

The target influent sediment concentration was 200 mg/L (+/-20 mg/L) for all tests. The concentration was verified by collecting a minimum of three timed dry samples at the injector and correlating the data with the measured average flow to produce the resulting influent concentration values for each test. The allowed Coefficient of Variance (COV) for the measured samples is 0.10. The moisture content of the test sediment was determined using ASTM D4959-07 for each test conducted and was utilized in the final removal calculation.

The protocol requires the temperature of the supply water to be below 80 degrees F.

Five (5) time-stamped effluent samples were collected from the end of the pipe during each run. A minimum of three detention times were allowed to pass before collecting the sample when the sediment feed was interrupted for measurements. Three (3) background samples of the supply water were collected with each odd-numbered effluent sample (1, 3 & 5). Collected samples were analyzed for Suspended Solids Concentration (SSC) using the ASTM D3977-97 (2013).

At the conclusion of a run, the injection feed was stopped and time-stamped. The flow was stopped after one (1) detention time had passed. The drawdown flow was measured at the V-notch weir every five (5) seconds until the effluent was reduced to 1% of the test flow. Two (2) evenly-spaced effluent samples were collected from the pipe during drawdown.

## 3.2 INSTRUMENTATION AND MEASURING TECHNIQUES

Instrument calibrations are presented in Appendix B.

#### 3.2.1 Influent Flow

The inflow to the test unit was measured using one of six (6) calibrated differential-pressure flow meters (2", 4", 6", 8", 10" or 12"). Each meter is fabricated per ASME guidelines and calibrated in Alden's Calibration Department prior to the start of testing. The high and low pressure lines from each meter were connected to manifolds containing isolation valves. Flows were set with a butterfly valve and the differential head from the meter was measured using a Rosemount® 0 to 250-inch Differential Pressure (DP) cell, also calibrated at Alden prior to testing. All pressure lines and cells were purged of air (bled) prior to the start of each test. The test flow was averaged and recorded every 5 seconds throughout the duration of the test using an in-house computerized data acquisition (DA) program. The accuracy of the flow measurement is  $\pm 2\%$ . A photograph of the flow meters is shown on **Figure 6** and the pumps on **Figure 7**.



Figure 6: Photograph Showing Laboratory Flow Meters



Figure 7: Photograph Showing Laboratory Pumps

## 3.2.2 Drawdown Flow

The drawdown flow was measured with the use of a V-notch weir installed at the end of the effluent tank. The weir was fabricated in accordance with the Bureau of Reclamation Water Measurement Manual guidelines. The weir was calibrated through the full range of flows prior to initiating the removal testing. The calculated and measured weir curves are shown on **Figure 8**.



Figure 8: Drawdown V-notch Weir Flow vs Head Curves

## 3.2.3 Temperature

Water temperature measurements within the supply sump were obtained using a calibrated Omega® DP25 temperature probe and readout device. The calibration was performed at the laboratory prior to testing. The temperature reading was documented at the start and end of each test, to assure an acceptable testing temperature of less than 80 degrees F.

#### 3.2.4 Pressure Head

Pressure head measurements were recorded at multiple locations using piezometer taps and a Omegadyne PX419, 0 - 2.5 psi cell. The pressure cell was calibrated at Alden prior to testing. Accuracy of the readings is  $\pm$  0.001 ft. The cell was installed at a known datum in relation to the tank floor, allowing for elevation readings through the full range of flows. A minimum of 30 seconds of pressure data was averaged and recorded for each pressure tap during hydraulic testing, under steady-state flow conditions, using the computerized DA program. Driving head and effluent weir measurements were averaged and recorded every 5-seconds during removal efficiency testing. A photograph of the pressure instrumentation is shown on **Figure 9**.



Figure 9: Pressure Measurement Instrumentation

## 3.2.5 Sediment Injection

The test sediment was injected into the crown of the influent pipe using an Auger® volumetric screw feeder, model VF-1, shown on **Figure 10**. The auger feed screw, driven with a variable-speed drive, was calibrated with the test sediment prior to testing, to establish a relationship between the auger speed (0-100%) and feed rate in grams/minute. The calibration, as well as

test verification of the sediment feed was accomplished by collecting timed dry samples of 0.1liter, up to a maximum of 1-minute, and weighing them on an Ohaus® 4000g x 0.1g, model SCD-010 digital scale. The feeder has a hopper at the upper end of the auger to provide a constant supply of dry test sand. The allowable Coefficient of Variance (COV) for the injection is 0.10.



Figure 10: Photograph Showing Variable-speed Auger Feeder

#### 3.2.6 Sample Collection

Effluent samples were collected in 2-liter containers from the end of the 6-inch effluent pipe. Background concentration samples were collected from the center of the vertical pipe upstream of the test unit with the use of a calibrated isokinetic sampler, shown on **Figure 11**.



Figure 11: Photograph Showing the Background Isokinetic Sampler

#### 3.2.7 Sample Concentration Analyses

Effluent and background concentration samples were analyzed by Alden in accordance with Method B, as described in ASTM Designation: D 3977-97 (Re-approved 2013), "Standard Test Methods for Determining Sediment Concentration in Water Samples". The required silica sand used in the sediment testing did not result in any dissolved solids in the samples and therefore, simplified the ASTM testing methods for determining sediment concentration. Associated instrumentation included:

- 2-Liter collection beakers
- Ohaus® 4000g x 0.1g digital scale, model SCD-010
- Oakton® StableTemp gravity convection oven, model 05015-59
- Sanplatec Dry Keeper® desiccator, model H42056-0001
- AND® 0.0001-gram analytical balance, model ER-182A
- Advantec 3-way filtration manifold
- Whatman® 934-AH, 47-mm, 1.5-micron, glass microfiber filter paper

Samples were collected in graduated 2-Liter beakers which were cleaned, dried and weighed to the nearest 0.1-gram, using an Ohaus® 4000g x 0.1g digital scale, model SCD-010, prior to sampling. Collected samples were also weighed to the nearest 0.1-gram using the Ohaus® digital scale. Each collected sample was filtered through a pre-rinsed Whatman® 934-AH, 47mm, 1.5-micron, glass microfiber filter paper, using a laboratory vacuum-filtering system. Prior to processing, each filter was rinsed with distilled water and placed in a designated dish and dried in an Oakton® StableTemp gravity convection oven, model 05015-59, at 225 degrees F for a minimum of 2.5 hours. Each dried filter was placed in a Sanplatec Dry Keeper® desiccator, model H42056-0001, to cool and then weighed to the nearest 0.0001-gram to determine the tare weight, using an AND® analytical balance, model ER-182A. Once filtered. each sample and dish was dried at a temperature between 175 and 210 degrees F (below boiling) for 20 to 30 minutes until visually dry. The oven temperature was increased to 225 degrees F and the samples were dried for an additional 2.5 hours. The dry samples and dishes were then cooled in the desiccator and weighed to the nearest 0.0001-gram, using the AND® balance. Net sediment weight (mg) was determined by subtracting the dried filter weight (tare) from the dried sample weight and multiplying the result by 1,000. The net sample volume, in liters, was determined by subtracting the beaker and net sediment weight from the overall sample weight and dividing by 1,000. Each sample sediment concentration, in mg/liter, was determined by dividing the net sediment weight by the net sample volume.

Photographs of the utilized laboratory instrumentation are shown on Figure 12 and Figure 13.



Figure 12: Laboratory Sample Filtration Equipment and Scale



Figure 13: Sample Analysis Laboratory Equipment

## 3.3 DATA MANAGEMENT AND ACQUISITION

A designated Laboratory Records Book was used to document the conditions and pertinent data entries for each test run conducted. All entries are initialed and dated.

A personal computer running an Alden in-house Labview® Data Acquisition (DA) program was used to record all data related to instrument calibration and testing. A 16-bit National Instruments® NI6212 Analog to Digital (A/D) board was used to convert the signal from the pressure cells. Alden's in-house data collection software, by default, collects one second averages of data collected at a raw rate of 250 Hz. The system allows very long contiguous data collection by continuously writing the collected 1-second averages and their RMS values to disk. The data output from the program is in tab delimited text format with a user-defined number of significant figures.

Test flow and pressure data was continuously collected at a frequency of 250 Hz. The flow data was averaged and recorded to file every 5 seconds. Steady-state pressure data was averaged and recorded over a duration of 30 seconds for each point. The recorded data files were imported into a spreadsheet for further analysis and plotting.

Excel based data sheets were used to record all sediment related data used for quantifying injection rate, effluent and background sample concentrations. The data was input to the designated spreadsheet for final processing.

## 3.4 PREPARATION OF TEST SEDIMENT

The sediment particle size distribution (PSD) used for removal efficiency testing was comprised of 1-1000 micron silica particles, as shown in **Table 1**. The Specific Gravity (SG) of the sediment mixes was 2.65. A commercially-available blend of each mix was provided by AGSCO Corp., a QAS International ISO-9001 certified company, and adjusted by Alden as required. Samples were collected from random bags and analyzed in accordance with ASTM D422-63 (2007), by GeoTesting Express, an ISO/IEC 17025 accredited independent laboratory. The average %-finer values of the stock material were found to be outside of the NJDEP acceptance criteria of 2% for particle sizes  $\leq$  20 microns. The test mix was adjusted to within the NJDEP acceptance criteria with the addition of commercially-available US-Silica Min-U-Sil 10, with a PSD of approximately 1-25 microns. Test batches of approximately 30 lbs each, were prepared in individual 5-gallon buckets, which were arbitrarily selected for the removal testing. A well-mixed random sample was collected from three random test batches and analyzed for PSD by GeoTesting Express. The average of the samples was used for compliance to the protocol specifications listed in Column 2 of Table 1. The D<sub>50</sub> of the samples ranged from 61 to 63 microns, with an average of 62 microns. The PSD data of the samples are shown in Table 2 and the corresponding curves are shown on Figure 14.

Particle size (µm)	NJDEP	Sample 1	Sample 2	Sample 3	Average
1000	100%	100%	100%	100%	100%
500	95%	96%	95%	96%	96%
250	90%	92%	91%	92%	92%
150	75%	79%	79%	79%	79%
110	60%	65%	65%	65%	65%
75	50%	53%	53%	53%	53%
53	45%	48%	47%	47%	47%
20	35%	34%	32%	36%	34%
8	20%	20%	19%	19%	19%
5	10%	14%	13%	13%	13%
2	5%	4%	4%	4%	4%
75	D <sub>50</sub>	61	63	63	62

Table 2: PSD Analyses of Alden NJDEP 1-1000 Mix



Figure 14: PSD Curves of 1-1000 micron Test Sediment and NJDEP Specifications

## 3.5 DATA ANALYSIS

The following equations and procedures were used in analyzing the data collected on the Lane SK75 test unit:

## 3.5.1 Hydraulics

The pressure cell was mounted at a height of 4.942 ft above the floor of the test unit. This datum value was added to all recorded measurements to correct the water height above the unit floor. The system energy loss across the unit was determined by adding the velocity head to the piezometric measurements taken in the inlet and outlet pipes.

The velocity head is defined by:

$$\mathbf{H} = \mathbf{V}^2 / 2\mathbf{g} \tag{1}$$

where,

The velocity is defined by:

$$\mathbf{V} = \mathbf{Q}/\mathbf{A} \tag{2}$$

where,

V = velocity (ft/sec), Q = flow (ft<sup>3</sup>/sec), and A = wetted area (ft<sup>2</sup>).



The area in the partial pipe flow was calculated using:

$$A = 0.125(\theta - Sin\theta)D^2$$
(3)

where,

A = wetted area (ft<sup>2</sup>),  $\theta$  = angle of inclusion (radians), and D = pipe diameter (ft).

The angle of inclusion of the water surface ( $\theta$ ) was calculated using:

$$\theta = 2\pi - 2\left(ACos\left(\frac{y-\frac{D}{2}}{\frac{D}{2}}\right)\right) \tag{4}$$

where,

Y = measured water depth (ft), and D = pipe diameter (ft).

#### 3.5.2 Removal Efficiency

The injected mass of each run was calculated by:

$$\mathbf{M}_{\rm ini} = \mathbf{\Delta}\mathbf{M} - (\mathbf{\Delta}\mathbf{M} \times \mathbf{w}) \tag{5}$$

where,

 $M_{inj}$  = final mass of injected sediment (grams),  $\Delta M$  = measured mass of injected sediment (grams), w = moisture content of sediment (%).

The injected concentration was calculated by:

$$\mathbf{C}_{inj} = \mathbf{M}_{inj} / \mathbf{Vol} \tag{6}$$

where,

 $C_{inj}$  = injected concentration (mg/L),  $M_{inj}$  = final mass of injected sediment (grams), Vol = total volume of water during sediment dosing (L).

The sediment removal efficiency was calculated by:

% Removal = (((
$$M_{inf}$$
)-( $M_{eff}$ )-( $M_{dd}$ )) /  $M_{inf}$ ) x 100 (7)

where,

M<sub>inf</sub> = Influent Mass: Average Influent TSS Concentration x Total Volume of water flowing through the filtration MTD during the addition of test sediment or Total Mass Added.

 $M_{eff}$  = Effluent Mass: Adjusted (for background TSS concentration) Effluent TSS Concentration x Total Effluent Volume of water flowing through the filtration MTD during the addition of test sediment.

 $M_{dd}$  = Drawdown Mass: Average Drawdown TSS Concentration x Total Volume of water flowing from the filtration MTD during drawdown

The effluent and background sample concentrations were calculated as follows:

The auger injector verification concentrations were determined by the following:

$$\mathbf{C}_{i} = \mathbf{M}_{f} / \mathbf{Q}_{avg} \tag{9}$$

where,

 $C_i$  = influent concentration (mg/L),  $M_f$  = sediment mass feed (mg/min),  $Q_{avg}$  = average flow (lpm)

## 3.6 LABORATORY ANALYSIS

The following Test Methods were used to analyze the various dry and aqueous sediment samples:

• Sediment Concentration

ASTM Designation: D 3977-97 (Re-approved 2013), "Standard Test Methods for Determining Sediment Concentration in Water Samples"

• Sediment Moisture Content

ASTM Designation: D4959-07, "Standard Test Method for Determination of Water (Moisture) Content of Soil by Direct Heating"

• Dry Sediment Particle Size Distribution

ASTM D422-63 (2007), "Standard Test Method for Particle Size Analysis of Soils"

## 3.7 QUALITY ASSURANCE AND CONTROL

All instruments were calibrated prior to testing and periodically checked throughout the test program. The instrumentation calibrations are shown in Appendix B.

## 3.7.1 Flow

The flow meters and pressure cells were calibrated in Alden's Calibration Laboratory, which is ISO 17025 accredited. All pressure lines were purged of air prior to initiating each test. A standard water manometer board and Engineers Rule were used to measure the differential pressure and verify the computer measurement of the selected flow meter.

## 3.5.1 Sediment Injection

The sediment feed (g/min) was verified with the use of a digital stop watch and 4000g calibrated digital scale. The tare weight of the sample container was recorded prior to collection of each sample. The samples were a minimum of 0.1 liters in size, with a maximum collection time of 1-minute.

#### 3.7.2 Sediment Concentration Analysis

All sediment concentration samples were processed in accordance with the ASTM D3977-97 (2013) analytical method. Gross sample weights were measured using a 4000g x 0.1g calibrated digital scale. The dried sample weights were measured with a calibrated 0.0001g analytical balance. Any change in filter weight due to processing was accounted for by including three control filters with each test set. The average of the three values, which was +/-0.1-0.5 mg, was used in the final concentration calculations.

Analytical accuracy was verified by preparing two blind control samples and processing using the ASTM method. The final calculated values were within 0.26% and 0.87% of the theoretical sample concentrations, with an average of 0.57% accuracy. This value was not corrected for particles smaller than the filter designation of 1.5 microns and therefore, is considered conservative.

## 4.0 RESULTS AND DISCUSSION

#### 4.1 SEDIMENT REMOVAL PERFORMANCE

Ten (10) removal efficiency test runs were conducted at a target flow of 120 gpm, corresponding to a normalized flow of 4 gpm/ft<sup>2</sup>. The minimum duration of each run was 30 minutes, with a target influent sediment concentration of 200 mg/l. All test runs met or exceeded the protocol testing criteria.

The measured flow for the 10 runs ranged from 119.5 gpm to 120.8 gpm, with an average flow of 119.9 gpm. The calculated COVs ranged from 0.001 to 0.004. The maximum recorded temperature for each run ranged from 67.2 to 78.4 degrees F. The calculated mass/volume influent concentrations ranged from 189 to 207 mg/L, with an average concentration of 201 mg/L. The measured injected influent concentrations ranged from 198 to 201 mg/L, with an average concentration of 200 mg/L. The injection COVs ranged from 0.001 to 0.003. The average adjusted effluent concentrations ranged from 29.2 to 41.5 mg/L and the average drawdown concentrations ranged from 5.0 to 25.7 mg/L. The drawdown duration for the ten (10) runs increased sequentially from 29 minutes to 74 minutes. The calculated removal efficiencies utilizing the mass/volume concentration ranged from 85.5% to 82.7%, with an average removal of 84.0%. The removal efficiency utilizing the injected concentration ranged from 85.5% to 82.8%, with an average removal of 83.9%. The maximum recording driving head was 3.26 ft, which correlates to 0.76 ft above the crown of the chamber.

The removal efficiencies were calculated using both the mass/volume and injected influent concentrations, and are shown in **Table 3**. The measured and calculated data for the ten runs is shown in **Table 4** and **Table 5**. The influent concentration and removal curves are shown on **Figure 15**.

Run #	Removal Efficiency				
	mass/volume	Injection Rate			
1	85.5%	85.5%			
2	85.4%	85.0%			
3	82.7%	83.6%			
4	83.8%	83.5%			
5	84.2%	83.9%			
6	84.1%	83.9%			
7	83.6%	83.3%			
8	82.9%	83.2%			
9	83.2%	82.8%			
10	84.5%	84.2%			
Average	84.0%	83.9%			

# Table 3: Removal Efficiency Summary

## **Table 4: Measured Influent Parameters**

Run #	Measured Flow		Max Temp	Influent Concentration (m		on (mg/L)
	gpm	COV	Deg. F	mass/volume	Injection Rate	Injection COV
1	120.8	0.004	78.4	198	198	0.002
2	119.6	0.001	78.1	207	201	0.002
3	119.7	0.002	74.8	189	200	0.003
4	119.7	0.001	74.6	203	200	0.001
5	119.5	0.001	74.8	204	201	0.001
6	120.2	0.001	70.5	202	200	0.001
7	119.7	0.001	70.7	204	200	0.002
8	120.1	0.001	69.7	196	199	0.002
9	119.8	0.001	68.6	204	200	0.002
10	119.9	0.001	67.2	203	200	0.001
Average	119.9			201	200	

Run #	Maximum Background		Adjusted	Drawdowr	Concentrat	ions (mg/L)				
	mg/L	#1	#2	#3	#4	#5	Average	#1	#2	Average
1	1.7	21.39	19.71	19.94	43.56	41.30	29.18	12.33	39.14	25.73
2	3.0	19.75	23.25	25.22	63.47	44.35	35.21	9.19	5.51	7.35
3	4.3	38.33	35.94	39.79	40.91	39.69	38.93	9.39	4.76	7.07
4	0.9	37.31	40.21	41.01	41.24	41.60	40.28	7.32	3.43	5.37
5	1.0	36.04	37.24	41.02	40.58	41.34	39.24	7.86	3.11	5.48
6	0.2	37.81	37.48	41.27	40.86	40.02	39.49	7.60	3.28	5.44
7	0.6	37.44	39.24	40.07	42.90	43.45	40.62	7.69	3.77	5.73
8	1.0	39.21	39.05	41.13	42.64	40.48	40.50	6.50	3.39	4.95
9	0.9	38.24	41.77	42.78	41.84	42.91	41.51	9.69	4.58	7.14
10	6.6	32.24	35.76	46.27	39.88	36.87	38.20	12.14	5.56	8.85





Figure 15: Lane SK75 Removal Efficiency and Influent Concentration Curves

#### 4.2 Hydraulic Measurements

Steady-state pressure measurements were recorded on the clean chamber to establish the hydraulic characteristic curves. Recorded flows ranged from 10 to 353 gpm (0.33 to 11.75  $gpm/ft^2$ ). The recorded data is shown in **Table 6** and corresponding curves on **Figure 16**.

Flow			Inlet El. (A')	Outlet El. (D')	System Energy Loss
gpm	cfs	gpm/sq-ft	Corrected for Energy ft	Corrected for Energy ft	A'-D'
0	0				
10.1	0.02	0.34	1.281	0.389	0.892
25.4	0.06	0.85	1.331	0.446	0.886
49.6	0.11	1.65	1.385	0.513	0.873
100.1	0.22	3.34	1.494	0.619	0.875
153.1	0.34	5.10	1.578	0.708	0.870
203.1	0.45	6.77	1.832	0.787	1.046
246.1	0.55	8.20	2.112	0.855	1.257
305.5	0.68	10.18	2.583	0.939	1.644
352.5	0.79	11.75	2.984	1.010	1.975

Table 6: Measured Hydraulic Data





#### **5.0 CONCLUSIONS**

The Lane SK75 Stormwater Treatment Unit achieved a sediment removal efficiency of 84.0% for the ten (10) runs conducted at 120 gpm (4 gpm/ft<sup>2</sup>), using 1-1000 micron NJDEP sediment, meeting the NJDEP filtration testing protocol criteria.

All testing conducted on the Lane SK75 Stormwater Treatment System met or exceeded the requirements as set forth in the 2013 NJDEP Testing Protocol.

James T. Mailloux

ames T. ufailloup

Senior Engineer Alden Research Laboratory Holden, MA 01520

# NOMENCLATURE AND ABBREVIATIONS

А	= area	(L <sup>2</sup> )	
Cd	= coefficient of discharge		
Ci	= influent sediment concentration	(M/L <sup>3</sup> )	
Cfs	cubic feet per second	(L <sup>3</sup> /T)	
COV	= coefficient of variance		
D	= diameter	(L)	
D <sub>50</sub>	= median particle size (L)		
DA	= data acquisition		
DP	= differential pressure	(ΔL)	
°F	= degree Fahrenheit	(T)	
Ft	= feet	(L)	
Ft/s	= feet per second	(L/T)	
g	= grams	(M)	
g	= gravity	(L/T <sup>2</sup> )	
gpm	gallons per minute	(L <sup>3</sup> /T)	
н	= head	(L)	
Hz	= hertz	(T)	
L	= liters	(L <sup>3</sup> )	
Lbs	= pounds	(M)	
mg/L	= milligram per liter	(M/L <sup>3</sup> )	
min	= minute	(T)	
PSD	= particle size distribution		
Q	= flow	(L <sup>3</sup> /T)	
sec	= seconds	(T)	
SLR	= surface loading rate $(L^3/T/L^2)$		
SSC	= suspended solids concentration		
V	= velocity	(L/T)	
w	moisture content (%)		

#### REFERENCES

- ASTM (2013), "Standard Test Methods for Determining Sediment Concentration in Water Samples", Annual Book of ASTM Standards, D3977-97, Vol. 11.02.
- ASTM (2007), "Standard Test Method for Particle Size Analysis of Soils", Annual Book of ASTM Standards, D422-63, Vol. 04.08.
- ASTM (2007), "Standard Test Methods for Determination of Water (Moisture) Content of Soil by Direct Heating", Annual Book of ASTM Standards, D4959-07, Vol. 04.08.
- ASME (1971), "Fluid Meters Their Theory and Application- Sixth Edition".
- NJDEP (2013), "Laboratory Protocol to Assess Total Suspended Solids Removal by a Hydrodynamic sedimentation Manufactured Treatment Device".
- U.S. Department of the Interior, Bureau of Reclamation "Water Measurement Manual", 3<sup>rd</sup> edition (2001)

#### Appendix A ALDEN QUALIFICATIONS

Founded in 1894, Alden is the oldest continuously operating hydraulic laboratory in the United States and one of the oldest in the world. From the early days of hydropower development and aviation, through World Wars I and II, and into the modern world defined by environmental needs, Alden has been a recognized leader in the field of fluid dynamics consulting, research and development. In the 21st Century, Alden is a vibrant, growing organization consisting of engineers, scientists, biologists, and support staff in five specialty areas. Much of our work supports the power generating, environmental, manufacturing, and process industries.

Alden offers a scope of specialized services including: conceptual design, detailed design, verification testing, analytical modeling, Computational Fluid Dynamics (CFD), field measurements, physical modeling, precision flow meter and instrumentation calibrations (ISO 17025 certified), and field testing. Decades of combined experience in numerical simulation techniques, physical modeling, and field studies provide the broad knowledge that is essential for recognizing which method is best suited to solving a problem.

Unusually large facilities (more than 125,000 square feet of enclosed space) and sophisticated data acquisition systems are available for each study. Approximately twenty buildings, located on thirty acres at our headquarters in Holden, MA are equipped with flow supplies and control systems for conducting hydraulic modeling, verification and equipment testing, fish testing, air/gas flow modeling, and numerous other types of flow testing. Fixed facilities providing air and water flow and an inventory of movable flow related equipment such as pumps, valves, meter devices, fish screens, etc. are located on the premises at our Massachusetts laboratory. Fully equipped and staffed carpentry, machine, and instrumentation shops provide rapid and efficient project support.

Alden has performed verification testing on approximately twenty Hydrodynamic Separator and Filtration Manufactured Treatment Devices (MTDs) for multiple manufacturers under various state and federal testing protocols. Alden's senior stormwater engineer, James Mailloux, has served on the ASTM and SWEMA Stormwater Technical committees, providing guidance in the area of testing methodologies. He has a Master's Degree in Environmental Engineering from Worcester Polytechnic Institute and has been conducting testing at Alden for more than 25 years. Mr. Mailloux has contributed to articles related to laboratory testing in Stormwater Magazine, as well as presented on multiple testing and regulatory topics at various conferences, including StormCon, WefTec and National Precast Concrete Association training seminars.

Appendix B INSTRUMENTATION CALIBRATIONS

CALIBRATION OF: 4" ORIFICE PLATE METER, SN 1 250" DP CELL, CELL NO. 812

FOR:

ALDEN RESEARCH LABORATORY INTERNAL PURCHASE ORDER NUMBER 66124

JUNE 2015 - REPORT NO. 2151ARL004-R1

CERTIFIED BY Philip S. Stacy

ALDEN RESEARCH LABORATORY, INC. 30 SHREWSBURY STREET HOLDEN, MASSACHUSETTS 01520

All Client supplied information and calibration results are considered proprietary and confidential to the Client. If a third party is a witness during calibrations or if the Client requests transmittal of data to a third party, Alden considers that the Client has waived confidentiality for the Witness.

In the event the Client distributes any report issued by Alden outside its own organization, such report shall be used in its entirety, unless Alden approves a summary or abridgment for distribution.

No advertising or publicity containing any reference to Alden or any employee, either directly or by implication, shall be made use of by Client without Alden's written approval.

#### INTRODUCTION

One 4" Orifice Plate Meter and a DP Cell were calibrated at the Alden Research Laboratory, Inc. (Alden) for Alden Research Laboratory, under Alden Internal PO Number 66124, Job 1142AS3SVT. Alden's standard test procedures, in QMSM-01 Revision 5, were used for testing. Flow element performance is presented in both tabular and graphical format.

#### FLOW ELEMENT INSTALLATION

The meter under test was installed in Test Line 4 in the Hooper Low Reynolds Number Facility, shown in plan view on Figure 1. Water is provided through a 40" penstock from the laboratory head pond at a head of about 18 feet. Electrically driven centrifugal pumps provide a maximum head of about 170 ft and a maximum flow of 1,200 gpm. The Gravimetric Method is used to measure flow.

The detailed piping arrangement immediately upstream and downstream of the meter under test, including all significant fittings and pipe lengths, is shown in Figure 2. Careful attention was given to align the meter under test with the test line piping, and to assure no gaskets between flanged sections protruded into the flow. Vents were provided at critical locations of the test line to purge the system of air.

#### TEST PROCEDURE

The test technician verified proper installation of the meter under test in the test line prior to introducing water into the system to equalize test line piping and primary element temperature to water temperature.

Prior to the test run, the control valve was set to produce the desired flow, while the flow was directed to waste. Sufficient time was allowed to stabilize both the flow and the instrument readings, after which the weigh tank discharge valve was closed and the weigh tank scale indicator and the electric timer were both zeroed. To begin the test run, flow was diverted into the weigh tank, which automatically started the timer.

At the start of the water collection a computer based data acquisition system was activated to read the meter output, such that the meter output was averaged while the weigh tank was filling. At the end of the run, flow was diverted away from the weigh tank and the timer and data acquisition system were stopped to terminate the test run. The weight of water in the tank, elapsed time, water temperature, and

average meter output were recorded on a data sheet. The data were entered into the computer to determine the flow and the results were plotted so that each test run was evaluated before the next run began. The control valve was then adjusted to the next flow and the procedure repeated.

#### FLOW MEASUREMENT METHOD

Flow was measured by the gravimetric method using a tank mounted on a scale having a capacity of 45,000 pounds with resolution of 0.5 lb. Alden's flow meter calibrations using the gravimetric flow measurement method comply with ASME/ANSI MFC-9M-1988 Measurement of Liquid Flow in Closed Conduits by Weighing Method. Water passing through the flow element was diverted into the tank with a hydraulically operated knife edge passing through a rectangular jet produced by a diverter head box. A Hewlett-Packard 10 MHz Frequency Counter with a resolution 0.001 sec was started upon flow diversion into the tank by an optical switch, which is positioned at the center of the jet. The timer was stopped upon flow diversion back to waste and the elapsed diversion time was recorded. An RTD thermometer measured water temperature to allow calculation of water density. Volumetric flow was calculated by Equation (1).

$$q_a = \frac{W}{T\rho_w B_c}$$
(1)

where

 $q_a = actual flow, ft^3/sec$   $W = mass of water collected, lb_m$  T = time, sec  $\rho_w = water density, lb_m/ft^3$  $B_c = buoyancy correction, 1-\rho_a/\rho_w$ 

The buoyancy correction includes air density calculated by perfect gas laws with the standard barometric pressure, a relative humidity of 75%, and measured air temperature. The weigh tank is periodically calibrated to full scale using 10,000 lbm of cast iron weights, whose calibration is traceable to NIST. Flow calculations are computerized to assure consistency. Weigh tank calibration data and water density as a function of temperature, are stored on disk file. Data were recorded manually and on disk file for later review and reporting.

#### DISCHARGE COEFFICIENT CALCULATIONS

Discharge coefficient, C, is defined by Equation (2) and plotted versus pipe or throat Reynolds number. Calculations of the discharge coefficient of differential producing flow meters are in accordance with ASME/ANSI MFC-3M-2004 <u>Measurement of Fluid Flow in Pipes Using Orifice</u>, <u>Nozzle and Venturi</u>, and ASME 19.5-2004 <u>Flow Measurement</u>. The discharge coefficient relates the theoretical flow to the actual flow.

$$C = \frac{q_a}{q_{th}} = \frac{q_a}{F_a K_M \sqrt{\Delta h}}$$
(2)

where

C=discharge coefficient, dimensionless $q_{th}$ =theoretical flow, ft³/sec $F_a$ =thermal expansion factor, dimensionless $\Delta h$ =differential head, ft at line temperature $K_M$ =meter constant, ft².5/sec

The theoretical proportionality constant,  $K_M$ , between flow and square root of differential head is a function of the meter throat area, the ratio of throat to pipe diameter, and the local gravitational constant, as defined by Equation (3).

$$K_{\rm M} = \frac{a_{\rm t}\sqrt{2g_{\rm l}}}{\sqrt{1-\beta^4}} \tag{3}$$

where	a <sub>t</sub>	=	throat area, $\pi d^2/4$ , ft <sup>2</sup>
	d	=	throat diameter, ft
	gı	=	local gravitational constant, 32.1625 ft/sec <sup>2</sup> at Alden
	β	Ш	ratio of throat to pipe diameter, d/D, dimensionless
	D	=	pipe diameter, ft

The effect of fluid properties, viscosity and density, on the discharge coefficient is determined by Reynolds number, the ratio of inertia to viscous forces. Pipe Reynolds number,  $R_D$ , is determined by Equation (4).

Report No. 2151ARL004-R1

$$R_{\rm D} = \frac{q_{\rm a} D}{a_{\rm p} \gamma} \tag{4}$$

where  $a_p = pipe area, \pi D^2/4, ft^2$  $\gamma = kinematic viscosity, ft^2/sec$ 

#### FLOW METER SIGNAL RECORDING

The secondary element, which converts the primary element signal into engineering units, was one of several "Smart" differential pressure transmitters having a range of 250" and 1,000" Water Column. Each transmitter was calibrated with a pneumatic or a hydraulic dead weight tester having an accuracy of 0.02% of reading. Transmitter signals were recorded by a PC based data acquisition system having a 16 bit A to D board. Transmitter calibrations were conducted with the PC system such that an end to end calibration was achieved. Transmitter output was read simultaneously with the diversion of flow into the weigh tank at a rate of about 34 Hz for each test run (flow) and averaged to obtain a precise differential head. Average transmitter reading was converted to feet of flowing water using a linear regression analysis of the calibration data and line water temperatures to calculate appropriate specific weight.

#### TEST RESULTS

The results are presented in tabular and graphical format. The calculated flow, meter signal and meter performance are listed in the tables in the following pages.

Analysis indicates that the flow measurement uncertainty is within 0.25% of the true value for each test run. Calibrations of the test instrumentation (temperature, time, weight, and length measurements) are traceable to the National Institute of Standards and Technology (formerly the National Bureau of Standards) and Alden's Quality Assurance Program is designed to meet ANSI/NCSL Z540-1-1994 "Calibration Laboratories and Test Equipment-General Requirements" (supercedes MIL-STD-45662A).



Figure 1 Hooper Low Reynolds Facility Test Line 4

Report No. 2151ARL004-R1

Page 5 of 15
# THIS PAGE LEFT INTENTIONALLY BLANK



4" ORIFICE PLATE METER

Serial Number: 1

ALDEN RESEARCH LAB

5 = 4.0260 TER = 2.6170	Pipe Dev #	x 10^5	3.0942
DATE: June 1, 201 PIPE DIAMETER THROAT DIAME	H Line	FT H20	19.725
	Flow	GPM	403.4
	Output	note]	9.586~
	Run	Durauon secs.	171.655
	Net	weigni lb.	9605
~	Air	Temp Deg F	ęę

Pipe Rey.# x 10^5	3.0942 2.7068 2.2660 1.8331 1.4154	0.9802
H Line FT H20	19.725 14.820 10.303 6.720 4.002	1.910
Flow GPM	403.4 350.0 236.4 182.8	126.5
Output [see note]	9.586~ 7.698~ 5.960~ 4.581~ 3.535~	2.730~
Run Duration secs.	171.655 176.461 186.594 184.800 178.904	201.568
Net Weight Ib.	9605 8568 7564 6060 4536	3539
Air Temp Deg F	66 67 67	67
Line Temp Deg F	67 67 68 68	68
Run #	- 0 o 4 v	9

Page 8 of 15

0.6123 0.6130

Coef

CALIBRATION

0.6138 0.6148 0.6159

0.6175

The data reported on herein was obtained by measuring equipment the calibration of which is traceable to NIST, following the installation and test procedures referenced in this report, resulting in a flow measurement uncertainty of +/- 0.25% or less.

CERTIFIED BY:

~ dp transmitter volts

CALIBRATED BY: THL

<sup>.</sup> 



Report No. 2151ARL004-R1

0.630

Page 9 of 15

V:\Data\PTCData\Alden Meters\arl312 (sn 1).xlsx



Report No. 2151ARL004-R1



#### Thermal Expansion Factor

The dimensions of a differential producing flow meter are affected by the operating temperature, requiring a Thermal Expansion Factor ( $F_a$ ) to be included in the calculations. The calculation requires the temperature at which the meter dimensions were measured be known. If this information is not available, an ambient temperature of 68° F is assumed. The Thermal Expansion Factor is calculated according to the American Society of Mechanical Engineers Standard ASME MFC-3M-1989, Equation 17 (pg 11).

$$F_{a} = 1 + \frac{2}{1 - \beta^{4}} \left( \alpha_{PE} - \beta^{4}_{meas} \propto_{p} \right) (t - t_{meas})$$

where

β	=	ratio of throat diameter to pipe diameter, dimensionless
$\alpha_{PE}$	=	thermal expansion factor of primary element, (in./oF)
∝ <sub>p</sub>	=	thermal expansion factor of pipe, (in./in./°F)
t	=	temperature of flowing fluid, °F
t <sub>meas</sub>	=	temperature of measurements, °F

Thermal expansion factors,  $\alpha$ , excerpted from MFC-3M-1989, are listed in the Table below for six typically used materials at three temperatures. Linear interpolation is used to determine the coefficients at flowing temperature.

Material	Coef.	-50 °F	70 °F	200 °F
Bronze 4-10	A	9.15	9.57	10.03
300 Series Stainless Steel	A	8.90	9.11	9.34
Monel	A	7.15	7.48	7.84
.2 to 1.1% C Steel	A	5.80	6.07	6.38
5% Chrome Moly	A	5.45	5.73	6.04
410 to 430 Stainless Steel	A	5.00	5.24	5.50

## WATER DENSITY\*

Temperature	Density	Temperature	Density	Temperature	Density
Fahrenheit	$lb_m/ft^3$	Fahrenheit	$lb_m/ft^3$	Fahrenheit	$lb_m/ft^3$
32	62.4179	62	62.3549	92	62.0903
33	62.4201	63	62.3489	93	62.0788
34	62.4220	64	62.3427	94	62.0671
35	62.4235	65	62.3363	95	62.0552
36	62.4246	66	62.3296	96	62.0432
37	62.4255	67	62.3228	97	62.0311
38	62.4260	68	62.3157	98	62.0188
39	62.4262	69	62.3084	99	62.0063
40	62.4261	70	62.3010	100	61.9937
41	62.4257	71	62.2933	101	61.9810
42	62.4250	72	62.2855	102	61.9681
43	62.4240	73	62.2774	103	61.9551
44	62.4227	74	62.2692	104	61.9419
45	62.4211	75	62.2608	105	61.9286
46	62.4193	76	62.2522	106	61.9151
47	62.4171	77	62.2434	107	61.9015
48	62.4147	78	62.2344	108	61.8878
49	62.4121	79	62.2252	109	61.8739
50	62.4092	80	62.2159	110	61.8599
51	62.4060	81	62.2063	111	61.8458
52	62.4025	82	62.1966	112	61.8315
53	62.3988	83	62.1868	113	61.8172
54	62.3949	84	62.1767	114	61.8027
55	62.3907	85	62.1665	115	61.7880
56	62.3863	86	62.1561	116	61.7733
57	62.3816	87	62.1456	117	61.7584
58	62.3768	88	62.1348	118	61.7434
59	62.3716	89	62.1239	119	61.7284
60	62.3663	90	62.1129	120	61.7132
61	62.3607	91	62.1017	121	61.6978

\* Distilled water values used in all calculations

Week 6/1/1	'5 through 6/8/15		BLDG2	<b><i>TRACEABILITY</i></b>			
ARL NUA	<i><b>IBERMODEL</b></i>	SERLAL NUMBER	DESCRIPTION	Notes	Location	LAST CAL DATE	NEXT CAL DUE
00484	1823	22101115	B&K PRECISION TIMER/COUNTER - BACKUP	FREQUENCY CHECKED DAILY - HOOPER LINE 4	BLDG 2		
00489	1823	2210206	B&K PRECISION TIMER/COUNTER - PRIMARY	FREQUENCY CHECKED DAILY - HOOPER LINE 4	BLDG 2		
coc00	KCC300S	2539467	50,000# WEIGH TANK SCALE W/ JAG EXTREME 51 READOUT	READOUT: JAG EXTREME S/N 5309718- HD - HOOPER LINE 1 & 2 50,000 # SCALE	BLDG 2	2/10/2015	8/11/2015
00584	DP41-RTD	6240653	LINE TEMPERATURE THERMOMETER READOUT	STUDENT LAB	BLDG 2	5/26/2015	11/24/2015
00596	DP41-RTD	7091746	AMBIENT TEMPERATURE THERMOMETER READOUT	STUDENT LAB	BLDG 2	5/26/2015	11/24/2015
00825	3051SCD2A2001 A	0481273	DP TRANSMITTER 0-250"		BLDG 2	6/1/2015	6/22/2015

Report No. 2151ARL004-R1

Page 14 of 15

Page 1 of 1

# ALDEN

June 10, 2015

# CERTIFICATE OF CALIBRATION

To Whom It May Concern:

This is to certify work performed under Internal Purchase Order Number 66124, *Job Number* issued by Alden Research laboratory, Inc., for the calibration of (1) 4" Orifice Plate Meter, Serial Number 1, and (1) 250" DP Cell, Cell Number 812.

The meter was calibrated in Alden's Hooper Low Reynolds Number Facility and the test instrumentation used was calibrated with Transfer Standards traceable to the National Institute of Standards & Technology (NIST).

Testing was conducted on June 1 - 2, 2015, in accordance with Alden's Quality Management System Manual; QMSM-01 Revision 5, October 17, 2014.

Chlory

Philip S. Stacy Director, Calibration Services

PSS/cmk

# CALIBRATION OF: 6" ORIFICE METER SERIAL NUMBER 977

FOR:

ALDEN RESEARCH LABORATORY, INC. PURCHASE ORDER NUMBER 63372 MARCH 2013 - REPORT NO. 2131ARL004-R1

> CERTIFIED BY Philip S. Stacy

ALDEN RESEARCH LABORATORY, INC. 30 SHREWSBURY STREET HOLDEN, MASSACHUSETTS 01520

All Client supplied information and calibration results are considered proprietary and confidential to the Client. If a third party is a witness during calibrations or if the Client requests transmittal of data to a third party, Alden considers that the Client has waived confidentiality for the Witness.

In the event the Client distributes any report issued by Alden outside its own organization, such report shall be used in its entirety, unless Alden approves a summary or abridgment for distribution.

No advertising or publicity containing any reference to Alden or any employee, either directly or by implication, shall be made use of by Client without Alden's written approval.

#### INTRODUCTION

One 6" Orifice Meter was calibrated at the Alden Research Laboratory, Inc. (Alden) for Alden's Hydraulic Department under their internal purchase order number 63372. Alden's standard test procedures, in QMSM-01 Revision 4, were used for calibration. Flow element performance is presented as coefficient C versus pipe Reynolds number, in both tabular and graphical format.

#### FLOW ELEMENT INSTALLATION

The meter under test was installed in Test Line 4 in the Hooper Low Reynolds Number Facility, which is shown in plan view on Figure 1. Water was provided from a 40" penstock from the Laboratory head pond at a head of about 18 feet. An electrically driven centrifugal pump provided a maximum head of about 170 ft and a maximum flow of 1,200 gpm.

The detailed piping arrangement, immediately upstream and downstream of the meter, including all significant fittings and pipe lengths, is shown in Figure 2. Careful attention was given to align the meter with the test line piping, and to assure no gaskets between flanged sections protruded into the flow. Vents were provided at critical locations of the test line to purge the system of air.

#### TEST PROCEDURE

The test technician verified proper installation of the meter under test in the test line prior to introducing water into the system to equalize test line piping and primary element temperature to water temperature.

Prior to the test run, the control valve was set to produce the desired flow, while the flow was directed to waste. Sufficient time was allowed to stabilize both the flow and the instrument readings, after which the weigh tank discharge valve was closed and the weigh tank scale indicator and the electric timer were both zeroed. To begin the test run, flow was diverted into the weigh tank, which automatically started the timer.

At the start of the water collection a computer based data acquisition system was activated to read the meter output, such that the meter output was averaged while the weigh tank was filling. At the end of the run, flow was diverted away from the weigh tank and the timer and data acquisition system were stopped to terminate the test run. The weight of water in the tank, elapsed time, water temperature, and average meter output were recorded on a data sheet. The data were entered into the computer to

determine the flow and the results were plotted so that each test run was evaluated before the next run began. The control valve was then adjusted to the next flow and the procedure repeated.

#### FLOW MEASUREMENT METHOD

Flow was measured by the gravimetric method using a tank mounted on a scale having a capacity of 1,000 pounds with a resolution of 0.1 lbs. Alden's flow meter calibrations using the gravimetric flow measurement method comply with ASME/ANSI MFC-9M-1988 <u>Measurement of Liquid Flow in Closed Conduits by Weighing Method</u>. Water passing through the flow element was diverted into the tank with a hydraulically operated knife edge passing through a rectangular jet produced by a diverter head box. A Hewlett-Packard 10 MHz Frequency Counter with a resolution 0.001 sec was started upon flow diversion into the tank by an optical switch, which is positioned at the center of the jet. The timer was stopped upon flow diversion back to waste and the elapsed diversion time was recorded. A thermistor thermometer measured water temperature to allow calculation of water density. Volumetric flow was calculated by Equation (1).

$$q_a = \frac{W}{T\rho_w B_c} \tag{1}$$

 $q_a = actual flow, ft^3/sec$   $W = mass of water collected, lb_m$  T = time, sec  $\rho_w = water density, lb_m/ft^3$  $B_c = buoyancy correction, 1-\rho_a/\rho_w$ 

The buoyancy correction includes air density calculated by perfect gas laws with the standard barometric pressure, a relative humidity of 75%, and measured air temperature. The weigh tank is periodically calibrated to full scale using 10,000 lbm of cast iron weights, whose calibration is traceable to NIST. Flow calculations are computerized to assure consistency. Weigh tank calibration data and water density as a function of temperature, are stored on disk file. Data were recorded manually and on disk file for later review and reporting.

where

#### DISCHARGE COEFFICIENT CALCULATIONS

Discharge coefficient, C, is defined by Equation (2) and plotted versus pipe or throat Reynolds number. Calculations of the discharge coefficient of differential producing flow meters are in accordance with ASME/ANSI MFC-3M-2004 <u>Measurement of Fluid Flow in Pipes Using Orifice</u>, <u>Nozzle and Venturi</u>, and ASME 19.5-2004 <u>Flow Measurement</u>. The discharge coefficient relates the theoretical flow to the actual flow.

$$C = \frac{q_a}{q_{th}} = \frac{q_a}{F_a K_M \sqrt{\Delta h}}$$
(2)

С	=	discharge coefficient, dimensionless
$q_{th}$	=	theoretical flow, ft <sup>3</sup> /sec
Fa	=	thermal expansion factor, dimensionless
$\Delta h$	=	differential head, ft at line temperature
K <sub>M</sub>	=	meter constant, ft <sup>2.5</sup> /sec

The theoretical proportionality constant,  $K_M$ , between flow and square root of differential head is a function of the meter throat area, the ratio of throat to pipe diameter, and the local gravitational constant, as defined by Equation (3).

$$K_{M} = \frac{a_{t}\sqrt{2g_{l}}}{\sqrt{1-\beta^{4}}}$$
(3)

where	a <sub>t</sub>	=	throat area, $\pi d^2/4$ , ft <sup>2</sup>
	d	=	throat diameter, ft
	gı	=	local gravitational constant, 32.1625 ft/sec <sup>2</sup> at Alden
	β	=	ratio of throat to pipe diameter, d/D, dimensionless
	D	=	pipe diameter, ft

The effect of fluid properties, viscosity and density, on the discharge coefficient is determined by Reynolds number, the ratio of inertia to viscous forces. Pipe Reynolds number,  $R_D$ , is determined by Equation (4).

where

$$R_{\rm D} = \frac{q_{\rm a} D}{a_{\rm p} \gamma} \tag{4}$$

where  $a_p = pipe area, \pi D^2/4, ft^2$  $\gamma = kinematic viscosity, ft^2/sec$ 

#### FLOW METER SIGNAL RECORDING

The secondary element, which converts the primary element signal into engineering units, was one of several "Smart" differential pressure transmitters having a range of 250" and 1,000" Water Column. Each transmitter was calibrated with a pneumatic or a hydraulic dead weight tester having an accuracy of 0.02% of reading. Transmitter signals were recorded by a PC based data acquisition system having a 16 bit A to D board. Transmitter calibrations were conducted with the PC system such that an end to end calibration was achieved. Transmitter output was read simultaneously with the diversion of flow into the weigh tank at a rate of about 34 Hz for each test run (flow) and averaged to obtain a precise differential head. Average transmitter reading was converted to feet of flowing water using a linear regression analysis of the calibration data and line water temperatures to calculate appropriate specific weight.

#### TEST RESULTS

The results are presented in tabular and graphical format. The calculated flow, meter signal and meter performance are listed in the table(s) in the following pages.

Analysis indicates that the flow measurement uncertainty is within 0.25% of the true value for each test run. Calibrations of the test instrumentation (temperature, time, weight, and length measurements) are traceable to the National Institute of Standards and Technology (formerly the National Bureau of Standards) and Alden's Quality Assurance Program is designed to meet ANSI/NCSL Z540-1-1994 "Calibration Laboratories and Test Equipment-General Requirements" (supercedes MIL-STD-45662A).



Figure 1 Hooper Low Reynolds Number Facility Test Line 4

THIS PAGE INTENTIONALLY LEFT BLANK

Plan View Hooper Facility Line 4



6" ORIFICE METER Serial Number: 977 Run Line Air Net Run

ALDEN RESEARCH LAB Purchase Order Number: 63372 PIPE DIAMETER = 6.0650THROAT DIAMETER = 4.2000

CALJBRATION DATE: March 19, 2013

Coef			0.6146	0.6149	0.6149	0.6150	0.6158	0.6163	0.6166	0.6173	0.6182
Pipe	Rey. #	x 10^5	3.5828	3.6287	3.2263	2.9138	2.5901	2.2854	1.9643	1.6543	1.3347
H Line		FT H20	18.321	19.350	16.146	13.165	10.375	8.067	5.953	4.212	2.734
Flow		GPM	1037.	1066.	974.6	880.2	782.4	690.4	593.3	499.7	403.1
Output	[see	note]	9.040~	9.435~	8.203~	7.057~	5.984~	5.097~	4.284~	3.614~	3.046~
Run	Duration	secs.	66.414	64.570	70.732	78.217	88.001	99.712	115.951	137.621	170.537
Net	. Weight	lb.	9574	9571	9577	9565	9566	9563	9558	9554	9552
Air	Temp	$\mathrm{Deg}\mathrm{F}$	60	61	57	56	56	57	57	57	57
Line	Temp	$\operatorname{Deg} F$	41	40	39	39	39	39	39	39	39
Run	#		1	2	n	4	Ś	9	7	8	6

~ dp transmitter volts

CERTIFIED BY: 🖌

Page 8 of 12



Report No. 2131ARL004-R1

Page 9 of 12

#### Thermal Expansion Factor

The dimensions of a differential producing flow meter are affected by the operating temperature, requiring a Thermal Expansion Factor ( $F_a$ ) to be included in the calculations. The calculation requires the temperature at which the meter dimensions were measured be known. If this information is not available, an ambient temperature of 68° F is assumed. The Thermal Expansion Factor is calculated according to the American Society of Mechanical Engineers Standard ASME MFC-3M-1989, Equation 17 (pg 11).

$$F_{a} = 1 + \frac{2}{1 - \beta^{4}} (\alpha_{PE} - \beta^{4}_{meas} \propto_{p})(t - t_{meas})$$

where	β	=	ratio of throat diameter to pipe diameter, dimensionless
	$\alpha_{\rm PE}$	=	thermal expansion factor of primary element, (in./in./°F)
	$\propto_{\rm p}$	=	thermal expansion factor of pipe, (in./in./°F)
	t	=	temperature of flowing fluid, °F
	t <sub>meas</sub>		temperature of measurements, °F

Thermal expansion factors,  $\alpha$ , excerpted from MFC-3M-1989, are listed in the Table below for six typically used materials at three temperatures. Linear interpolation is used to determine the coefficients at flowing temperature.

Material	Coef.	-50 °F	70 °F	200 °F
Bronze 4-10	A	9.15	9.57	10.03
300 Series Stainless Steel	A	8.90	9.11	9.34
Monel	A	7.15	7.48	7.84
.2 to 1.1% C Steel	A	5.80	6.07	6.38
5% Chrome Moly	A	5.45	5.73	6.04
410 to 430 Stainless Steel	А	5.00	5.24	5.50

Mean Coefficient of Therma	l Expansion = $\frac{A}{10^6}$ (in./in./°F)
----------------------------	---

# WATER DENSITY\*

Temperature	Density	Temperature	Density	Temperature	Density
Fahrenheit	lb <sub>m</sub> / ft <sup>3</sup>	Fahrenheit	$lb_m / ft^3$	Fahrenheit	lb <sub>m</sub> / ft <sup>3</sup>
32	62.4179	62	62.3549	92	62.0903
33	62.4201	63	62.3489	93	62.0788
34	62.4220	64	62.3427	94	62.0671
35	62.4235	65	62.3363	95	62.0552
36	62.4246	66	62.3296	96	62.0432
37	62.4255	67	62.3228	97	62.0311
38	62.4260	68	62.3157	98	62.0188
39	62.4262	69	62.3084	99	62.0063
40	62.4261	70	62.3010	100	61.9937
41	62.4257	71	62.2933	101	61.9810
42	62.4250	72	62.2855	102	61.9681
43	62.4240	73	62.2774	103	61.9551
44	62.4227	74	62.2692	104	61.9419
45	62.4211	75	62.2608	105	61.9286
46	62.4193	76	62.2522	106	61.9151
47	62.4171	77	62.2434	107	61.9015
48	62.4147	78	62.2344	108	61.8878
49	62.4121	79	62.2252	109	61.8739
50	62.4092	80	62.2159	110	61.8599
51	62.4060	81	62.2063	111	61.8458
52	62.4025	82	62.1966	112	61.8315
53	62.3988	83	62.1868	113	61.8172
54	62.3949	84	62.1767	114	61.8027
55	62.3907	85	62.1665	115	61.7880
56	62.3863	86	62.1561	116	61.7733
57	62.3816	87	62.1456	117	61.7584
58	62.3768	88	62.1348	118	61.7434
59	62.3716	89	62.1239	119	61.7284
60	62.3663	90	62.1129	120	61.7132
61	62.3607	91	62.1017	121	61.6978

\* Distilled water values used in all calculations

Week 3/18/13	through 3/25/13		BLDG 2	TRACEABILITY			
ARL NUM	BERMODEL	SERIAL NUMBER	DESCRIPTION	Notes	Location	LAST CAL DATE	NEXT CAL DUE
00484	1823	22101115	B&K PRECISION TIMER/COUNTER -	FREQUENCY CHECKED DAILY - HOOPER LINE 4	BLDG 2		
00489	1823	2210206	BACKUP B&K PRECISION TIMER/COUNTER - PRIMARY	FREQUENCY CHECKED DAILY - HOOPER LINE 4	BLDG 2		
00584	DP41-RTD	6240653	LINE TEMPERATURE THERMOMETER READOUT	STUDENT LAB	BLDG 2	11/28/201	5/29/2013
00596	DP41-RTD	7091746	AMBIENT TEMPERATURE THERMOMETER	STUDENT LAB	BLDG 2	11/28/201	5/29/2013
<i>c7800</i>	3051SCD2A20 01A	0481273	DP TRANSMITTER 0-		BLDG 2	3/19/2013	4/9/2013
01018	6286	1005 FCB	10,000# WEIGH TANK SCALE WITH LOAD CELL 1048	10,000# CAPACITY THURMAN SCALE - HOOPER FACILITY LINE 4	BLDG 2	12/20/201	6/20/2013

Page 1 of 1

#### CALIBRATION OF:

10" VENTURI SERIAL NUMBER 10x5 8" ORIFICE METER SERIAL NUMBER 8x5.25

FOR

ALDEN RESEARCH LABORATORY, INC. PURCHASE ORDER NUMBER 67374 AUGUST 2015 - REPORT NO. 2151ARL014-R1

> CERTIFIED BY Philip S. Stacy

ALDEN RESEARCH LABORATORY, INC. 30 SHREWSBURY STREET HOLDEN, MASSACHUSETTS 01520

All Client supplied information and calibration results are considered proprietary and confidential to the Client. If a third party is a witness during calibrations or if the Client requests transmittal of data to a third party, Alden considers that the Client has waived confidentiality for the Witness.

In the event the Client distributes any report issued by Alden outside its own organization, such report shall be used in its entirety, unless Alden approves a summary or abridgment for distribution.

No advertising or publicity containing any reference to Alden or any employee, either directly or by implication, shall be made use of by Client without Alden's written approval.

,

#### **INTRODUCTION**

Two flow meters were calibrated at the Alden Research Laboratory, Inc. (Alden). Alden's standard test procedures, in QMSM-01 Revision 5, were used for testing. The performance of the meter under test is presented in both tabular and graphical format.

#### FLOW ELEMENT INSTALLATION

The meter under test was installed in test line 1, 2, 3 or 4 of the Hooper Facility, depending on flow requirements and pipe size. In the Hooper Facility, water is provided from a 40" penstock from the laboratory head pond at a head of about 18 feet. Electrically driven centrifugal pumps provide a maximum head of about 140 ft and a maximum flow of 6,000 gpm in Lines 1 and 2, and a maximum head of about 170 ft and a maximum flow of 1,200 gpm in Line 4. In Line 3, water is provided through a 40" penstock from the main laboratory pond resulting in a gross gravity head of approximately 28 feet and a maximum flow of 35,000 gpm. A calibrated master Venturi is used to measure flow in Line 3 and the Gravimetric Method is used to measure flow in Lines 1, 2 and 4.

The detailed piping arrangements, including all significant fittings and pipe lengths, immediately upstream and downstream of the flow sections, are shown in the included figures. Careful attention was given to align the meter under test with the test line piping, and to assure no gaskets between flanged sections protruded into the flow. Vents were provided at critical locations of the test line to purge the system of air.

#### TEST PROCEDURE

The test technician verified proper installation of the meter under test in the test line prior to introducing water into the system to equalize test line piping and primary element temperature to water temperature.

Prior to the test run, the control valve was set to produce the desired flow, while the flow was directed to waste. Sufficient time was allowed to stabilize both the flow and the instrument readings, after which the weigh tank discharge valve was closed and the weigh tank scale indicator and the electric timer were both zeroed. To begin the test run, flow was diverted into the weigh tank, which automatically started the timer.

Report No. 2151ARL014-R1

At the start of the water collection a computer based data acquisition system was activated to read the meter output, such that the meter output was averaged while the weigh tank was filling. At the end of the run, flow was diverted away from the weigh tank and the timer and data acquisition system were stopped to terminate the test run. The weight of water in the tank, elapsed time, water temperature, and average meter output were recorded on a data sheet. The data were entered into the computer to determine the flow and the results were plotted so that each test run was evaluated before the next run began. The control valve was then adjusted to the next flow and the procedure repeated.

#### FLOW MEASUREMENT METHOD

Flow was measured by the gravimetric method using tanks mounted on a scale having a capacity of 100,000 pounds, with resolution of 1.0 lb. Alden's flow meter calibrations using the gravimetric flow measurement method comply with ASME/ANSI MFC-9M-1988 Measurement of Liquid Flow in Closed Conduits by Weighing Method. Water passing through the meter under test was diverted into the tank with a hydraulically operated knife edge passing through a rectangular jet produced by a diverter head box. A Hewlett-Packard 10 MHz Frequency Counter with a resolution 0.001 sec was started upon flow diversion into the tank by an optical switch, which is positioned at the center of the jet. The timer was stopped upon flow diversion back to waste and the elapsed diversion time was recorded. An RTD thermometer measured water temperature to allow calculation of water density. Volumetric flow was calculated by Equation (1).

$$q_{a} = \frac{W}{T\rho_{w}B_{c}}$$
(1)

where

 $q_a = actual flow, ft^3/sec$ W = mass of water collect

= mass of water collected,  $lb_m$ 

T = time, sec

 $\rho_{\rm w}$  = water density,  $lb_{\rm m}/ft^3$ 

 $B_c = buoyancy correction, 1-\rho_a/\rho_w$ 

The buoyancy correction includes air density calculated by perfect gas laws with the standard barometric pressure, a relative humidity of 75%, and measured air temperature. The weigh tank is periodically calibrated to full scale using 10,000 lbm of cast iron weights, whose calibration is traceable to NIST. Flow calculations are computerized to assure consistency. Weigh tank calibration

data and water density as a function of temperature, are stored on disk file. Data were recorded manually and on disk file for later review and reporting.

### DISCHARGE COEFFICIENT CALCULATIONS

Discharge coefficient, C, is defined by Equation (2) and plotted versus pipe or throat Reynolds number. Calculations of the discharge coefficient of differential producing flow meters are in accordance with ASME/ANSI MFC-3M-2004 <u>Measurement of Fluid Flow in Pipes Using Orifice</u>, <u>Nozzle and Venturi</u>, and ASME 19.5-2004 <u>Flow Measurement</u>. The discharge coefficient relates the theoretical flow to the actual flow.

$$C = \frac{q_a}{q_{th}} = \frac{q_a}{F_a K_M \sqrt{\Delta h}}$$
(2)

where С discharge coefficient, dimensionless = theoretical flow, ft<sup>3</sup>/sec  $q_{th}$ = Fa thermal expansion factor, dimensionless = Δh differential head, ft at line temperature \_ meter constant, ft<sup>2.5</sup>/sec K<sub>M</sub> =

The theoretical proportionality constant,  $K_M$ , between flow and square root of differential head is a function of the meter throat area, the ratio of throat to pipe diameter, and the local gravitational constant, as defined by Equation (3).

$$K_{\rm M} = \frac{a_{\rm t}\sqrt{2g_{\rm l}}}{\sqrt{1-\beta^4}} \tag{3}$$

where	a <sub>t</sub>	=	throat area, $\pi d^2/4$ , ft <sup>2</sup>
	d	=	throat diameter, ft
	gı	=	local gravitational constant, 32.1625 ft/sec <sup>2</sup> at Alden
	β	=	ratio of throat to pipe diameter, d/D, dimensionless
	D	=	pipe diameter, ft

#### Page 3 of 16

The effect of fluid properties, viscosity and density, on the discharge coefficient is determined by Reynolds number, the ratio of inertia to viscous forces. Throat Reynolds number,  $R_d$ , (or pipe;  $R_D$ ) is determined by Equation (4).

$$R_{d} = \frac{q_{a}d}{a_{t}\gamma} \qquad (R_{D} = \frac{q_{a}D}{a_{D}\gamma})$$
(4)

where  $a_t = throat area, \pi d^2/4, ft^2 (a_D = \pi D^2/4)$  $\gamma = kinematic viscosity, ft^2/sec$ 

#### FLOW METER SIGNAL RECORDING

The secondary element, which converts the primary element signal into engineering units, was one of several "Smart" differential pressure transmitters having a range of 250" and 1,000" Water Column. Each transmitter was calibrated with a pneumatic or a hydraulic dead weight tester having an accuracy of 0.02% of reading. Transmitter signals were recorded by a PC based data acquisition system having a 16 bit A to D board. Transmitter calibrations were conducted with the PC system such that an end to end calibration was achieved. Transmitter output was read simultaneously with the diversion of flow into the weigh tank at a rate of about 34 Hz for each test run (flow) and averaged to obtain a precise differential head. Average transmitter reading was converted to feet of flowing water using a linear regression analysis of the calibration data and line water temperatures to calculate appropriate specific weight.

#### **TEST RESULTS**

The results are presented in tabular and graphical format. The calculated flow, meter signal and meter performance are listed in the table(s) in the following pages.

Analysis indicates that the flow measurement uncertainty is within 0.25% of the true value for each test run. Calibrations of the test instrumentation (temperature, time, weight, and length measurements) are traceable to the National Institute of Standards and Technology (formerly the National Bureau of Standards) and Alden's Quality Assurance Program is designed to meet ANSI/NCSL Z540-1-1994 "Calibration Laboratories and Test Equipment-General Requirements" (supercedes MIL-STD-45662A).

Report No. 2151ARL014-R1



Figure 1 Allen High Reynolds Facility Test Lines 1, 2, 3 and 4

Page 5 of 16

THIS PAGE INTENTIONALLY BLANK

]

I

......

Plan View Hooper Facility Line 1



10" VENTURI METERSerial Number: 10x5Tag Number: #3August 31, 2015



As found is as left data

ALDEN RESEARCH LAB

Purchase Order Number: 67374

**10" VENTURI METER** 

Serial Number: 10x5

Tag Number: #3

PIPE DIAMETER = 10.0000 THROAT DIAMETER = 5.0000

DATE: August 31, 2015

CALIBRATION

The data reported on herein was obtained by measuring equipment the calibration of which is traceable to NIST , following the installation and test procedures referenced in this report, resulting in a flow measurement uncertainty of +/- 0.25% or less.

**CERTIFIED BY:** 

~ dp transmitter volts

CALIBRATED BY: THL

Page 8 of 16

Report No. 2151ARL014-R1

<sup>1.0240</sup> 1.0236 1.0233 .0245 l.0237 l.0243 1.0233 .0233 .0243 ..0262 ..0262 ..0011 Coef .0225 0.3190 1.3364 Rey.# 0.2615 0.1946 x 10^6 1.3214 0.9273 0.7256 0.5286 0.8255 0.3217 0.1329 0.0830 0.0646 0.5534 1.1201 Pipe FT H20 60.354 42.754 29.098 17.874 9.536 3.495 61.294 23.371 H Line 10.735 3.554 2.347 1.300 0.604 0.236 404.6 252.9 196.6 1601. 970.2 4065. 2507. 978.5 795.4 592.5 Flow GPM 3394. 2799. 2193. 698. 4034. 7.011~ 6.116~ 4.803~ 5.661~ 3.338~ 7.899~ 4.252~ 3.360~ 2.896~ 4.332~ 2.919~ Dutput 6.123~ 7.809~ 8.868~ 2.588~ note] [see 225.089 131.383182.929219.962 81.415 82.011 97.637 118.652 50.565 192.605 Duration 81.778 240.524 94.344 222.270 222.355 Run secs. Weight 42714 45874 45938 46036 45774 43154 30273 46084 45676 24814 24254 18258 12473 6753 6557 Net lb. Temp Deg F Air 72 72 72 72 72 76 77 77 77 77 78 78 74 74 74 74 Deg F Temp Line 72 72 72 72 72 772 772 772 772 772 17 17 17 17 17 17 17 Run # 6 9 10 10 11 11 11 11 11 11 11 12 - 0 m 4 v



Report No. 2151ARL014-R1

Page 9 of 16



Report No. 2151ARL014-R1

Page 10 of 16

I

and a second
9'8" Meter Section ÷. 6' - 4' \*8 .∞ - 12" x 8" 16" x 12" ÷ -16" Flow Straightener 8' - 10" .16" Flow Figure 3

Purchase Order Number: 67374 ALDEN RESEARCH LAB Serial Number: 8x5.25 **8" ORIFICE PLATE** September 1, 2015

19

1775

Plan View Hooper Facility Line 1

Page 11 of 16

PIPE DIAMETER = 8.0000 THROAT DIAMETER = 5.2510

CALIBRATION DATE: September 1, 2015

Coef	0.6120 0.6125 0.6135 0.6137 0.6137 0.6137	
Pipe Rey. # x 10^5	6.3592 5.3313 4.5326 3.7033 2.8972 2.8972 2.6525 2.4497	
H Line FT H20	17.946 12.531 9.043 6.027 3.686 1.841 2.629	
Flow GPM	1555. 1300. 1105. 903.4 706.8 500.7 597.6	
Output [see note]	8.896~ 6.813~ 5.472~ 4.311~ 3.411~ 9.094~ 3.005~	
Run Duration secs.	169.405 202.484 199.534 195.660 190.467 262.642 220.333	
Net Weight Ib.	36527 36509 30587 24506 18663 18231 18231	
Air Temp Deg F	72 72 72 72 72 72 72 72 72 72 72 72 72 7	
Line Temp Deg F	71 71 71 71 71 71	
Run #	-904N'0L	

The data reported on herein was obtained by measuring equipment the calibration of which is traceable to NIST, following the installation and test procedures referenced in this report, resulting in a flow measurement uncertainty of +/-0.25% or less.

CERTIFIED BY: 💋

CALIBRATED BY: THL

~ dp transmitter volts

Page 12 of 16

ALDEN RESEARCH LAB Purchase Order Number: 67374 8" ORIFICE PLATE Serial Number: 8x5.25



Report No. 2151ARL014-R1

Page 13 of 16

V:\Data\PTCData\Alden Meters\arl326 (sn8x5.25).xlsx



Page 14 of 16

#### THERMAL EXPANSION FACTOR

The dimensions of a differential producing flow meter are affected by the operating temperature, requiring a Thermal Expansion Factor ( $F_a$ ) to be included in the calculations. The calculation requires the temperature at which the meter dimensions were measured be known. If this information is not available, an ambient temperature of 68° F is assumed. The Thermal Expansion Factor is calculated according to the American Society of Mechanical Engineers Standard ASME MFC-3M-1989, Equation 17 (pg 11).

$$F_{a} = 1 + \frac{2}{1 - \beta^{4}} \left( \alpha_{PE} - \beta^{4}_{meas} \propto_{p} \right) (t - t_{meas})$$

where

β	=	ratio of throat diameter to pipe diameter, dimensionless
$\alpha_{PE}$	=	thermal expansion factor of primary element, (in./in./°F)
$\propto_{\rm p}$	=	thermal expansion factor of pipe, (in./in./°F)
t	=	temperature of flowing fluid, °F
t <sub>meas</sub>	=	temperature of measurements, °F

Thermal expansion factors,  $\alpha$ , excerpted from MFC-3M-1989, are listed in the Table below for six typically used materials at three temperatures. Linear interpolation is used to determine the coefficients at flowing temperature.

Material	Coef.	-50 °F	70 °F	200 °F
Bronze 4-10	Α	9.15	9.57	10.03
300 Series Stainless Steel	A	8.90	9.11	9.34
Monel	A	7.15	7.48	7.84
.2 to 1.1% C Steel	Α	5.80	6.07	6.38
5% Chrome Moly	A	5.45	5.73	6.04

Α

5.00

5.24

5.50

Mean Coefficient of Thermal Expansion = $\frac{A}{10^6}$ (in./in./°F	F)
--	----

410 to 430 Stainless Steel

## WATER DENSITY\*

Temperature	Density	Temperature	Density	Temperature	Density
Fahrenheit	$lb_m / ft^3$	Fahrenheit	$lb_m / ft^3$	Fahrenheit	$lb_m / ft^3$
32	62.4179	62	62.3549	92	62.0903
33	62.4201	63	62.3489	93	62.0788
34	62.4220	64	62.3427	94	62.0671
35	62.4235	65	62.3363	95	62.0552
36	62.4246	66	62.3296	96	62.0432
37	62.4255	67	62.3228	97	62.0311
38	62.4260	68	62.3157	98	62.0188
39	62.4262	69	62.3084	99	62.0063
40	62.4261	70	62.3010	100	61.9937
41	62.4257	71	62.2933	101	61.9810
42	62.4250	72	62.2855	102	61.9681
43	62.4240	73	62.2774	103	61.9551
44	62.4227	74	62.2692	104	61.9419
45	62.4211	75	62.2608	105	61.9286
46	62.4193	76	62.2522	106	61.9151
47	62.4171	77	62.2434	107	61.9015
48	62.4147	78	62.2344	108	61.8878
49	62.4121	79	62.2252	109	61.8739
50	62.4092	80	62.2159	110	61.8599
51	62.4060	81	62.2063	111	61.8458
52	62.4025	82	62.1966	112	61.8315
53	62.3988	83	62.1868	113	61.8172
54	62.3949	84	62.1767	114	61.8027
55	62.3907	85	62.1665	115	61.7880
56	62.3863	86	62.1561	116	61.7733
57	62.3816	87	62.1456	117	61.7584
58	62.3768	88	62.1348	118	61.7434
59	62.3716	89	62.1239	119	61.7284
60	62.3663	90	62.1129	120	61.7132
61	62.3607	91	62.1017	121	61.6978

\* Distilled water values used in all calculations

and the statement of the second se

Ī

to a second

A	١F	R	_

12X8 VENTURI METER #6

#### CALIBRATION DATE: October 26, 2007 PIPE DIAMETER = 12.0000 THROAT DIAMETER = 8.0000

Run #	Line Temp Deg F	Air Temp Deg F	Net Weight lb.	Run Duration secs.	Output [see note]	Flow GPM	H Line FT H20	Ріре Rey. # x 10^б	Coef
2	94	70	95258	113.301	9.819~	6086.	20.539	2.1724	0.9572
3	93	70	95330	123.785	8.560~	5574.	17.232	1.9853	0.9572
4	93	70	95355	132.042	7.771~	5227.	15.162	1.8595	0.9568
5	93	70	95340	146.093	6.707~	4724.	12.368	1.6804	0.9574
6	93	70	95152	157.832	6.016~	4363.	10.553	1.5506	0.9574
7	93	70	95191	176.317	5.220~	3908.	8.462	1.3886	0.9575
8	93	70	95122	199.660	4.504~	3448.	6.584	1.2253	0.9579
9	93	70	95136	232.159	3.850~	2966.	4.866	1.0528	0.9584
10	93	70	95069	270.713	3.357~	2542.	3.570	0.9022	0.9589
11	93	70	95007	322.214	2.955~	2134.	2.515	0.7575	0.9593
12	93	70	95055	410.403	2.587~	1676.	1.549	0.5943	0.9601
13	93	70	94972	535.373	2.342~	1284.	0.906	0.4547	0.9612
14	93	70	95339	113.245	9.838~	6093.	20.588	2.1580	0.9572

~ dp transmitter volts

The data reported on herein was obtained by measuring equipment the calibration of which is traceable to NIST, following the installation and test procedures referenced in this report, resulting in a flow measurement uncertainty of  $\pm$ -0.25% or less.

CALIBRATED BY: S.V.K.

CERTIFIED BY:





**12 x 8 Venturi Meter No. 6** 10/26/07 calibration

#### С\*=С \* К

\$



	A	В	С	D	C* (avg)	К
old	-8.00E-05	0.0011	-0.0057	1.3962	3.0765	3.230
new	-3.00E-21	2.00E-14	-4.00E-08	3.018	2.9951	3.230

CHECK	
Х	Y
500000	3.0026250000000000E+00

de.

C=Q/(K\*SQRT(H))

H (ft)	Q (cfs)
5	6.6972
10	9.4713
15	11.5999
20	13.3944

		12 x 8 #6		
	CAL Octobe	er 26, 2007	,	
	nu:	7.96E-06		
	K=3.230		C=Q/K*SQ	RT(H)
				PIPE
RUN	Q	DEL H	С	REN #
2	6086	20.539	0.9263	2,168,897
3	5574	17.232	0.9262	1,986,433
4	5227	15.162	0.9260	1,862,771
5	4724	12.368	0.9266	1,683,515
6	4363	10.553	0.9264	1,554,863
7	3908	8.462	0.9267	1,392,713
8	3448	6.584	0.9269	1,228,780
9	2966	4.866	0.9275	1,057,008
10	2542	3.57	0.9280	905,905
11	2134	2.515	0.9282	760,504
12	1676	1.549	0.9289	597,284
13	1284	0.906	0.9305	457,585
14	6093	20.588	0.9263	2,171,392

渉

Z:\Library\Useful Technical Info\Flow Meters\Venturi Inventory\12x8\12X8#6.xls

	ļ
$\Sigma$	l

in this report, resulting in a flow measurement uncertainty of +/- 0.25% or less.	
For Pipe Rey. $\#s$ above 0.64 x 10 <sup>6</sup> Avg Coef = 0.9829 With Standard Deviation The data reported on herein was obtained by measuring equipment the calibration of which is traceable to NIST, following the installation and test procedures referenced	~ dp transmitter volts

13 14	11 12	10	٥x		9 0	2	4	. U	2	. —	4	Run
92 92	92 92	93	2, 23	93 93	93	93	93	93	56	93	Temp Deg F	Line
73 73	73 73	73	73 73	73	73	73	73	73	73	73	Lemp Deg F	Air
95118 95810	95080 95172	95140	95251	95303	95398	95513	95437	95675	95821	95821	weight lb.	Net
281.180 68.512	185.182 223.427	140.903 157.095	127.847	115.751	104.869	97.235	89.924	84.231	78.379	73.871	Duration secs.	Run
2.155~ 4.689~	2.360~ 2.247~	2.023~ 2.501~	2.761~	2.930~	3.136~	3.325~	3.547~	3.772~	4.053~	4.313~	[see note]	Output
2448.3 10121.4	3716.1	4881.8 4383.4	5392.5	5959.6	6584.6	7110.2	7682.1	8221.9	8849.2	9389.5	GPM	Flow
0.413 7.070	0.952	1.643 1.324	2.005	2.449	2.990	3.488	4.070	4.662	5.398	6.082	FT H20	H Line
0.6143 0.6467 2.6733	0.9826	1.2922	1.4274	1.5810	1.7488	1.8884	2.0403	2.1861	2.3529	2.4993	Rey. # x 10^6	Pipe
0.9830 0.9830 0.9825	0.9833	0.9831	0.9829	0.9829	0.9828	0.9826	0.9828	0.9828	0.9830	0.9827		Coef

# CALIBRATION DATE: November 9, 2007 PIPE DIAMETER = 16.0000 THROAT DIAMETER = 12.5000

ARL

16X12.5 VENTURI MANIFOLDED TAPS

For	די מי מס מיייייי	K <sub>M</sub>	Q A A A A A A A A A A A A A A A A A A A				Dis	charg	e Coeff	icient	- C	
Pipe Rey tensions	= Aver = Thro; = Loca = Ratio Pipe Thro;	= Mete	= Actu; = Disch = Press		.0	0.970	0.975	0.980	0.985	0.990	0.995	
ynolds N By: AF	age The at Area l Accele of Thro Diameto at Diameto	r Const	al Flow narge Co ure Diff		00			-!				
Number RL	rmal Ex (ft <sup>2</sup> ) xration c pat to Pi er (Inc. eter (Inc.	ant =	(ft <sup>3</sup> /sec pefficien ferential	, = 0			 	-	- +		+ +	-¦   -
> 0.64	(pansio) of Gravi pe Dian hes ) nches )	a	e) nt ( Din l ( Feet	F <sub>a</sub> K <sub>N</sub>	0.50							  
x 10^6	n Facto ity (ft/se meter (	2g 1 - <sup>β4</sup>	nension of Wate									
avg co	r ec <sup>2</sup> ) Dimen		less ) er at Ru	h	1.0		   	-	- + 		+       <u>   </u>	-  
efficier	sionles		ın Temp		ð		 		- <u>-</u>	 		 -
μ	Š		oerature		P			-i	- +	i	+	-i
		11	<u> </u>		1.50 pe Ré		     			     		 
0.9829	1.0004 0.8522 32.1625 0.7812 16.000( 12.500(	8.6286			eynol		    	 	- <del> </del>		     	 -
				1	2.00 ds Nu		·   	-   <mark> </mark>			+	- - ·   
2					mber		·					-¦
					N		·1			     	     +  	   -)
					2.50		 					
					(in m				φ ; τ		 F	 -  
		16X No		MAN	3.00 illion						   ( <u>   </u> 	 
		(12.5 vemt	$\mathbf{A}$	IIFOI	(S)			·	$\frac{1}{1} - \frac{1}{1}$	   	! ! !	-¦ -
		VEN )er 9,	<b>RL</b>	DEI	ယ	+ 	 	 		   <b>-</b>	        	-i
		TUR 2007		) TAI	50				$\frac{1}{1} - \frac{1}{1}$			       
		Ι		S				·	+		   +i	-¦   -
					4.00		 l	     		 	 <u>   </u> 	  
~											         	
3					4		   		+		· · · · · · · · · · · · · · · · · · ·	-    -L

SN 400326 8/12/2016							
Н	Н	Volts					
(inch)	(ft)						
10.512	0.876	0.7883					
26.292	2.191	1.942					
38.712	3.226	2.859					
54.696	4.558	4.028					
60.168	5.014	4.427					





V:\M&TE\Model Studies\Mailloux 250in Cell SN 0812.xls

Printed: 6/4/2015

Reviewed:\_\_\_\_

CALIBRATION	ESS DIVISIO CALIBRATION/REPAIL 27 INDL TEL: (80 CER	CO CALIBRATION LABORATORY N OF WALSH ENGINEERING SERVICES, INC. R OF ALL TYPES OF ELECTRONIC / MECHANICAL TEST EQUIP STRIAL AVE, CHELMSFORD, MA 01824-3618 0) 325-2201 (978) 250-0880 www.esscolab.com TIFICATE OF CALIBRATION	MENT	NVLAP LAB CODE 200972-0		
ISSUE DATE: 11/10/2015	Certificate #: 1244842					
CUSTOMER / LOCATION ALDEN RESEARCH LABO 30 SHREWSBURY STREE HOLDEN, MA 01520 PURCHASE ORDER:	RATORY INC T	EQUIPMENT INFORMATION MANUFACTURER:AND MODEL NO:ER182A SERIAL NO:4704083 CONTROL NO:1502 TYPE: ANALYTICAL BALANCE				
AS FOUND	IN TOLERANCE	Remarks: ON SITE				
			CALIBRATION	V	human	
PERFORMED: ON SITE METHOD:ECP NO. 1.5.16	TEMPERATURE ( Rev.5 2/25/2010 REL HUMIDITY (%	deg C): 23 CALIBRATION DATE:11/6/2015   MET MET   SRH): 63   CALIBRATION DUE: 11/6/2016	rologist:	Jose Dali	rdey ge	
Standards Used To Calibrat I.D. Template E3285 @ TROEMNER 721	e Equipment	Type Equipment 6110X1G CLASS 1 WEIGHT SET	Report No. 1191723	Last Cal. Date 06/30/2014	Cal. Due Date 06/30/2016	

ESSCO CALIBRATION LABORATORY

MDY

The ESSCO Quality System is accredited to ISO 17025:2005 The results above relate only to the item(s) calibrated. Expanded uncertainties were calculated per ISO "Guide to the Expression of Uncertainty Measurement", (GUM) with 95% confidence level and a coverage factor of k=2. This certificate shall not be reproduced, except in full, without written approval of ESSCO. The user should consider the measurement uncertainty when assessing the metrological status of the equipment.

This document certifies that the unit conformed to applicable specifications upon successful completion of the calibration. Any number of factors may cause the calibration item to drift out of calibration before the recommended interval has expired. The standards used are traceable to NIST or a National Measurement Institute.

This calibration was performed in compliance with the ESSCO Quality System manual, ECL1 Rev 35, dtd 20 Mar 2015, ISO 9001:2008, ANSI/NCSL Z540.1, ISO 10012:2003, ISO 13485, TS 16949, and when required contractually, 10CFR21 and 10CFR50 App. B.

DATA

This report must not be used to claim product certification, approval, or endorsement by NVLAP, NIST, or any agency of the Federal Government.

Internal Use Only: 11/06/2015

Richard a. Bany

RICK BERRY **Releasing Authority** 

1

Control #: 1502

# Test Points

- Statistic

	Description	Nominal	Tolerance	Unit Measure	As Found	As Left	Uncertainty
1	REPEATABLE 20G	0.000000	0.000020 0.000000	g	0.000000	0.000000	0.0000037g
2	REPEATABLE 100G	0.00000	0.00010 0.00000	g	0.00000	0.00000	0.000037g
3	LIN TARE 0+10G=REF	10.00000	99.99999 0.00000	g	9.99999	9.99999	0.000024g
4	LIN TARE 10+10G-REF	0.00000	0.00003 -0.00003	g	-0.00001	-0.00001	0.000024g
5	LIN TARE 20+10G-REF	0.00000	0.00003 -0.00003	g	-0.00001	-0.00001	0.000024g
6	LIN TARE 0+30G=REF	30.0000	99.9999 0.0000	g	0.0000	0.0000	0.00013g
7	LIN TARE 30+30G-REF	0.0000	0.0002 -0.0002	g	0.0001	0.0001	0.00013g
8	LIN TARE 60+30G-REF	0.0000	0.0002 -0.0002	g	0.0001	0.0001	0.00013g
9	LIN TARE 90+30G-REF	0.0000	0.0002 -0.0002	g	0.0001	0.0001	0.00013g
10	LIN TARE 120+30G-REF	0.0000	0.0002 -0.0002	g	0.0000	0.0000	0.00013g
11	LIN TARE 150+30G-REF	0.0000	0.0002 -0.0002	g	0.0000	0.0000	0.00013g
12	SPAN ACCY	100.0000	100.0003 99.9997	g	100.0000	100.0000	0.00015g
13	100G LOADSHIFT L	0.0000	0.0003 -0.0003	g	-0.0001	-0.0001	0.00013g
14	100G LOADSHIFT R	0.0000	0.0003 -0.0003	g	-0.0001	-0.0001	0.00013g
15	100G LOADSHIFT C	0.0000	0,0003 -0.0003	g	0.0000	0.0000	0.00013g
16	100G LOADSHIFT F	0.0000	0.0003 -0.0003	g	0.0000	0.0000	0.00013g
17	100G LOADSHIFT B	0.0000	0.0003 -0.0003	g	0.0000	0.0000	0.00013g
			And provide a second of the Control				

Test Points

Seq. Description Nominal Tolerance Unit Measure As Found As Left Uncertainty

End of Data Note: A = Adjusted F = Failed L = Limited \*\* = Outside Scope of Accreditation



## ESSCO CALIBRATION LABORATORY

DIVISION OF WALSH ENGINEERING SERVICES, INC.

CALIBRATION/REPAIR OF ALL TYPES OF ELECTRONIC / MECHANICAL TEST EQUIPMENT

27 INDUSTRIAL AVE, CHELMSFORD, MA 01824-3618 TEL: (800) 325-2201 (978) 250-0880 www.esscolab.com



NVLAP LAB CODE 200972-0

## CERTIFICATE OF CALIBRATION

Page 1 of 2

## ISSUE DATE: 11/10/2015 Certificate #: 1244832

CUSTOMER / LOCATIO ALDEN RESEARCH L 30 SHREWSBURY ST HOLDEN, MA 01520 PURCHASE ORDER:	N ABORATORY INC TREET		EQUIPMENT INFORMATION MANUFACTURER: ADAM MODEL NO: GBK-35A SERIAL NO: AE948423 CONTROL NO: AE948423 TYPE: 16X0.0005KG DIGITAL COUNTING SCALE					
AS FOUND AS LEFT	IN TOLERANCE IN TOLERANCE		Remarks: ON SITE					
L	METHOD / ENVIRONMENT		CALIBRATION					
PERFORMED: ON S METHOD:ECP NO. 1.5	ITE TEMPERATURE (deg .16 Rev.5 2/25/2010 REL HUMIDITY (%RH)	C): 23 I): 63	CALIBRATION DATE 11/6/2015 METROLOGIST: Jose Salindy pe CALIBRATION DUE: 11/6/2016					
Standards Used To Ca	librate Equipment							
I.D. Template E2850 @ TROEMNE E3285 @ TROEMNE E3287 @ TROEMNE	Ty R 7212-1T 611 R 7212-1W 611 R 10 KG WE	Vpe Equipmen 10X1G CLASS 1 10X1G CLASS 1 EIGHT	Report No. Last Cal. Date Cal. Due Date   WEIGHT SET 1117492 07/17/2014 07/17/2016   WEIGHT SET 1191723 06/30/2014 06/30/2016   1191758 06/30/2014 06/30/2016					

### The ESSCO Quality System is accredited to ISO 17025:2005

MDY

The results above relate only to the item(s) calibrated. Expanded uncertainties were calculated per ISO "Guide to the Expression of Uncertainty Measurement", (GUM) with 95% confidence level and a coverage factor of k = 2. This certificate shall not be reproduced, except in full, without written approval of ESSCO. The user should consider the measurement uncertainty when assessing the metrological status of the equipment.

This document certifies that the unit conformed to applicable specifications upon successful completion of the calibration. Any number of factors may cause the calibration item to drift out of calibration before the recommended interval has expired. The standards used are traceable to NIST or a National Measurement Institute.

This calibration was performed in compliance with the ESSCO Quality System manual, ECL1 Rev 35, dtd 20 Mar 2015, ISO 9001:2008, ANSI/NCSL 2540.1, ISO 10012:2003, ISO 13485, TS 16949, and when required contractually, 10CFR21 and 10CFR50 App. B.

This report must not be used to claim product certification, approval, or endorsement by NVLAP, NIST, or any agency of the Federal Government.

Internal Use Only: 11/06/2015

DATA

Richard a. Bar

RICK BERRY Releasing Authority

Control #: AE948423

## Test Points

হ্ৰান্ন	Deservioien	Nonthell	Tolerance	Unit Measure	As Found	Aston	Ungeneihiy	
1	REPEAT STDEV 5KG	0.00	1.00 -1.00	<b>g</b>	0.00	0.00	0.18 g	
2	LINEARITY & ACCY	0.0	1.5 -1.5	g	0.0	0.0	0.29 g	t del televit dependente est sufficiente se forma presentations
3	LINEARITY & ACCY	2000.0	2001.5 1998.5	g	2000.0	2000.0	0.29 g	ugan ng pagamag na kasala aking kana pana kasala kana kasa
4	LINEARITY & ACCY	4000.0	4001.5 3998.5	g	4000.0	4000.0	0.29 g	n y maan ka ka ya ka
5	LINEARITY & ACCY	8000.0	8001.5 7998.5	g	8000.0	8000.0	0.29 g	a (an ) taming t processing a transmission memory and memory and
6	LINEARITY & ACCY	12000.0	12001.5 11998.5	g	11999.5	11999.5	0.29 g	ng, yan yangan digan ngija (sa sa s
7	LINEARITY & ACCY	16000.0	16001.5 15998.5	g	16000.0	16000.0	0.29 g	u' m' chuch an dual de lan lannelana na la papa paga ana an an
8	LINEARITY & ACCY	8000.0	8001.5 7998.5	<b>g</b>	8000.0	8000.0	0.29 g	agence account of the statement and the
9	LINEARITY & ACCY	4000.0	4001.5 3998.5	g	4000.0	4000.0	0.29 g	nicensis et est and a filma actualization of a provide effect and
10	LINEARITY & ACCY	2000.0	2001.5 1998.5	g	2000.0	2000.0	0.29 g	
11	LINEARITY & ACCY	0.0	1.5 -1.5	g	0.0	0.0	0.29 g	yee y type you again you constant on the Weiner Weiner Weiner State
12	5KG LOAD-SHIFT L	0.0	1.5 -1.5	g	0.0	0.0	0.29 g	annana ana di ana ana si 1964 aya ay 1965 bida da
13	5KG LOAD-SHIFT R	0.0	1.5 -1.5	g	0.0	0.0	0.29 g	- ANIE - IN -
14	5KG LOAD-SHIFT F	0.0	1.5 -1.5	g	0.0	0.0	0.29 g	و چې چې د وې د وې د وې د وې د وې د وې د
15	5KG LOAD-SHIFT B	0.0	1.5 -1.5	g. G	0.0	0.0	0.29 g	an - y sana ang sa
			and a second	opensign and a design of the set				

End of Data

Note: A = Adjusted F = Failed L = Limited \*\* = Outside Scope of Accreditation

CALIERATION	ESS DIVISIO CALIBRATION/REPAI 27 INDU TEL: (80 CER	CO CALIBRATION LABORATORY ON OF WALSH ENGINEERING SERVICES, INC. IR OF ALL TYPES OF ELECTRONIC / MECHANICAL TEST EQUIPMENT JSTRIAL AVE, CHELMSFORD, MA 01824-3618 00) 325-2201 (978) 250-0880 www.esscolab.com RTIFICATE OF CALIBRATION	NVLAP LAB CODE 200972-0
ISSUE DATE: 11/10/2015	Certificate #: 1244839		
CUSTOMER / LOCATION ALDEN RESEARCH LABO 30 SHREWSBURY STRE HOLDEN, MA 01520	DRATORY INC ET	EQUIPMENT INFORMATION MANUFACTURER:OHAUS MODEL NO:SP4001 SERIAL NO:7126070017 CONTROL NO:0742	
PURCHASE ORDER:			
AS FOUND AS LEFT	IN TOLERANCE IN TOLERANCE	Remarks: ON SITE	
M1	ETHOD / ENVIRONMENT	CALIBR	ATION
PERFORMED: ON SITE METHOD:ECP NO. 1.5.16	TEMPERATURE ( Rev.5 2/25/2010 REL HUMIDITY (%	(deg C): 23CALIBRATION DATE:11/6/2015 METROLOGIS%RH): 63CALIBRATION DUE: 11/6/2016	T: Jose Galindey ge
Standards Used To Calibra I.D. Template E3285 @ TROEMNER 72	nte Equipment	Type Equipment Report I 6110X1G CLASS 1 WEIGHT SET 119172	No. Last Cal. Date Cal. Due Date 23 06/30/2014 06/30/2016

ESSCO CALIBRATION LABORATORY

The ESSCO Quality System is accredited to ISO 17025:2005

MDY

The results above relate only to the item(s) calibrated. Expanded uncertainties were calculated per ISO "Guide to the Expression of Uncertainty Measurement", (GUM) with 95% confidence level and a coverage factor of k = 2. This certificate shall not be reproduced, except in full, without written approval of ESSCO. The user should consider the measurement uncertainty when assessing the metrological status of the equipment.

This document certifies that the unit conformed to applicable specifications upon successful completion of the calibration. Any number of factors may cause the calibration item to drift out of calibration before the recommended interval has expired. The standards used are traceable to NIST or a National Measurement Institute.

This calibration was performed in compliance with the ESSCO Quality System manual, ECL1 Rev 35, dtd 20 Mar 2015, ISO 9001:2008, ANSI/NCSL Z540.1, ISO 10012:2003, ISO 13485, TS 16949, and when required contractually, 10CFR21 and 10CFR50 App. B.

This report must not be used to claim product certification, approval, or endorsement by NVLAP, NIST, or any agency of the Federal Government.

11/06/2015 Internal Use Only:

DATA

Control #: 0742

## Test Points

	Description	Nombrai	Tolerance	Unit Measure	As Found	AsiLefit	Uncertainty	
1	REPEATABILITY STDEV 4kg	0.00	0.10 0.00	g	0.00	0.00	< 0.018 g	N of an and a second second second second
2	LINEARITY & ACCURACY	0.0	0.1 -0.1	g	0.0	0.0	0.058 g	on all the standing of the sta
3	LINEARITY & ACCURACY	1000.0	1000.1 999.9	g	1000.0	1000.0	0.058 g	
4	LINEARITY & ACCURACY	2000.0	2000.1 1999.9	g	2000.0	2000.0	0.058 g	Star and a second s
5	LINEARITY & ACCURACY	3000.0	3000.1 2999.9	<b>g</b>	3000.1	3000.1	0.058 g	
6	LINEARITY & ACCURACY	4000.0	4000.1 3999.9	g	4000.1	4000.1	0.058 g	para nyang naka nangar na mba naka
7	LINEARITY & ACCURACY	2000.0	2000.1 1999.9	9	2000.1	2000.1	0.058 g	14(4)-0 44(4)-0 16(4)-0 (4)-0 (4)
8	LINEARITY & ACCURACY	0.0	0.1 -0.1	<b>B</b>	0.1	0.1	0.058 g	
9	2kg LOAD-SHIFT C	0.0	0.1 -0.1	g	-0.1	-0.1	0.058 g	
10	2kg LOAD-SHIFT L	0.0	0.1 -0.1	<b>G</b>	0.1	0.1	0.058 g	
11	2kg LOAD-SHIFT R	0.0	0.1 -0.1	<b>g</b>	0.1	0.1	0.058 g	
12	2kg LOAD-SHIFT F	0.0	0.1 -0.1	g	0.1	0.1	0.058 g	n namananta katal man 1 (1995) - 199
13	2kg LOAD-SHIFT B	0.0	0.1 -0.1	g	0,1	0.1	0.058 g	an 1000 ka
	-		•••		the second s	consistent and in recording a consistence because and a consistence of the result of the result of the result of		

End of Data

Note: A = Adjusted F = Failed L = Limited \*\* = Outside Scope of Accreditation

CALIBRATION LABORATORY	ESSCO CALIBRA DIVISION OF WALSH EN CALIBRATION/REPAIR OF ALL TYPES O 27 INDUSTRIAL AVE, CH TEL: (800) 325-2201 (978) CERTIFICATE (	NVLAP LAB CODE 200972-0	
ISSUE DATE: 11/10/2015	Certificate #: <b>1245494</b>		Page 1 of 3
CUSTOMER / LOCATION		EQUIPMENT INFORMATION	
ALDEN RESEARCH LABOR	RATORY INC	MANUFACTURER: OHAUS	
30 SHREWSBURY STREE		MODEL NO:SP4001	
HOLDEN, MA 01520		SERIAL NO:7123101312	
		CONTROL NO:0826	
PURCHASE ORDER: HY	′D-PO-0069	TYPE: DIGITAL BALANCE	
AS FOUND (	OUT OF TOLERANCE	Remarks: LIMITED TO 500G ONLY	
AS LEFT	IN TOLERANCE	ON SITE	
MF <sup>-</sup>	THOD / ENVIRONMENT	CALIBRATIC	DN
PERFORMED: ON SITE	TEMPERATURE (deg C): 23	CALIBRATION DATE:11/6/2015	Pare Malinder 10
METHOD:ECP NO. 1.5.16	Rev.5 2/25/2010 REL HUMIDITY (%RH): 63	CALIBRATION DUE: 11/6/2016	fore Saundy fr
Standards Used To Calibrate	e Equipment		
I.D. Template E3285 @ TROEMNER 7212	Type Equipmer 6110X1G CLASS 1	nt Report No. I WEIGHT SET 1191723	Last Cal. Date Cal. Due Date 06/30/2014 06/30/2016

The ESSCO Quality System is accredited to ISO 17025:2005

MDY

The results above relate only to the item(s) calibrated. Expanded uncertainties were calculated per ISO "Guide to the Expression of Uncertainty Measurement", (GUM) with 95% confidence level and a coverage factor of k=2. This certificate shall not be reproduced, except in full, without written approval of ESSCO. The user should consider the measurement uncertainty when assessing the metrological status of the equipment.

This document certifies that the unit conformed to applicable specifications upon successful completion of the calibration. Any number of factors may cause the calibration item to drift out of calibration before the recommended interval has expired. The standards used are traceable to NIST or a National Measurement Institute.

This calibration was performed in compliance with the ESSCO Quality System manual, ECL1 Rev 35, dtd 20 Mar 2015, ISO 9001:2008, ANSI/NCSL Z540.1, ISO 10012:2003, ISO 13485, TS 16949, and when required contractually, 10CFR21 and 10CFR50 App. B.

DATA

This report must not be used to claim product certification, approval, or endorsement by NVLAP, NIST, or any agency of the Federal Government.

Internal Use Only: 11/09/2015

Richard a. Bony

RICK BERRY **Releasing Authority** 

Control #: 0826

## Test Points

<b>Reflector</b> d			1. 10 N 1995 - 19 S. S.		and the Reput	Act off	Internation
્રસ્ટાંગુ	Description	Nominal	Tolonamee.	onnoviersenter:			
1	REPEATABILITY STDEV 4kg	0.00	0.10 0.00	g	0.00	0.00	< 0.018 g
2	LINEARITY & ACCURACY	0.0	0.1 -0.1	g	0.0	0.0	0.058 g
3	LINEARITY & ACCURACY	1000.0	1000.1 999.9	<b>g</b>		an an ann an	0,058 g
4	LINEARITY & ACCURACY	2000.0	2000.1 1999.9	g	L		0.058 g
5	LINEARITY & ACCURACY	3000.0	3000.1 2999.9	g			0.058 g
6	LINEARITY & ACCURACY	4000.0	4000.1 3999.9	g	L		0.058 g
7	LINEARITY & ACCURACY	2000.0	2000.1 1999.9	g	L	an kang tang pala mangkan salap sa mangkan kang mangkan kang salam sa mangkan kang salam sa sa sa	0.058 g
8	LINEARITY & ACCURACY	0.0	0.1 -0.1	g	0.0	0.0	0.058 g
9	LINEARITY & ACCURACY	0.0	0.1 -0.1	g	0.1	0.1	0.058 g
10	LINEARITY & ACCURACY	200.0	200.1 199.9	g	199.9	199.9	0.058 g
11	LINEARITY & ACCURACY	300.0	300.1 299.9	g	299.9	299.9	0.058 g
12	LINEARITY & ACCURACY	400.0	400.1 399.9	g	400.0	400.0	0.058 g
13	LINEARITY & ACCURACY	500.0	500.1 499.9	g	500.0	500.0	0.058 g
14	LINEARITY & ACCURACY	300.0	300.1 299.9	g	299.9	299.9	0.058 g
15	LINEARITY & ACCURACY	0.0	0.1 -0.1	g	0.0	0.0	0.058 g
16	2kg LOAD-SHIFT C	0.0	0.1 -0.1	g	0.1	0.1	0.058 g
17	2kg LOAD-SHIFT L	0.0	0.1 -0.1	g	0.1	0.1	0.058 g
				F. P. Color and M. D. Color on Physics and Physics State Astronomy Color and Color	And the American Antion and a second s		

Control #: 0826

#### Test Points

and stations		deleave considered		a constant and a second constant and a second s				
્રસ્ત્	Description	leminal	Tolerance U	nit Measure	As Found	As Lein	Unsereinny	1 and
18	2kg LOAD-SHIFT R	0.0	0.1 -0.1	g	-0.1	-0.1	0.058 g	an a
19	2kg LOAD-SHIFT F	0.0	0.1 -0.1	g	0.0	0.0	0.058 g	pour a constant constant de la Marcine de
20	2kg LOAD-SHIFT B	0.0	0.1 -0.1	g	0.0	0.0	0.058 g	
Manineha vors V 071		and the second						

End of Data

Note: A = Adjusted F = Failed L = Limited \*\* = Outside Scope of Accreditation LIMITED TO 500G ONLY